


An Abacus
BEST
SELLER

CADPAK-64

FOR THE COMMODORE 64®

ENHANCED
VERSION

*The full-featured
design and drawing
program*



you can count on
Abacus



CADPAK-64

**Computer Aided Design Package
with Dimensioning for the C-64 & C-128**

Designed by Roy Wainwright
Copyright © 1984

Published by:

Abacus 

5370 52nd Street SE
Grand Rapids, MI 49508

Copyright Notice

Abacus Software makes this package available for use on a single computer only. It is unlawful to copy any portion of this software package onto any medium for any purpose other than backup. It is unlawful to give away or resell copies of this package. Any unauthorized distribution of this product deprives the authors of their deserved royalties. For use on single-site multiple computers, please contact Abacus Software to make arrangements.

Warranty

Abacus Software makes no warranties, expressed or implied, as to the fitness of this software package for any particular purpose. In no event will Abacus Software be liable for consequential damages. Abacus Software will replace any copy of this software which is unreadable, if returned within 30 days of purchase. Thereafter, there will be a nominal charge for replacement.

Eighth Printing, November 1988

Copyright © 1985

Roy Wainwright

Copyright © 1985

Abacus Software, Inc.
5370 52nd Street, SE
Grand Rapids, MI 49508

ISBN

0-916439-18-6

TABLE OF CONTENTS

1.0 WHAT IS CADPAK-64?	1
2.0 WHAT'S INCLUDED IN THIS PACKAGE	3
3.0 HARDWARE REQUIRED	5
4.0 BEFORE GETTING STARTED	7
4.1 LIGHT PEN VERSION	7
4.2 KEYBOARD VERSION	8
4.3 LIGHTPEN OPERATION	8
4.4 SCREENS	9
4.5 RESTART	9
4.6 COLORS	10
4.7 DRAWING MODES	10
4.8 POSITION	11
4.9 DISK FILES	14
4.10 DIRECTORY DISPLAY	15
4.11 DISK DRIVE NUMBER	15
4.12 FUNCTION KEYS	16
5.0 CADPAK SETUP (PRINTER DIMENSIONS)	17
5.1 SETTING THE DIMENSIONS FOR YOUR PRINTER	19
6.0 LOADING CADPAK-64	21
7.0 CADPAK-64 MAIN MENU	23
7.1 DRAW	24
7.2 LINE	25
7.3 RAYS	26
7.4 BOX	26
7.5 CIRCLE	27
7.6 ELLIPSE(OVAL)	27
7.7 FILL	28
7.8 TEXT	30
7.9 ZOOM	32
7.10 USE OBJECTS	33

7.11 RUBOUT	35
7.12 POINTS	35
7.13 ARC	36
7.14 MEASURE	37
7.15 CLEAR	37
7.16 TRY AGAIN!	38
7.17 UTILITIES	39
7.18 COPY AREA	42
7.19 DISK/SAVE/RESTORE	45
7.20 SWAP SCREENS	47
7.21 OBJECT/FONT MGR	47
7.22 PRINT	50
8.0 CONFLICTS	51
9.0 PATTERN EDITOR	53
9.1 PATTERN EDITOR MENU	53
10.0 CADPAK TUTORIAL - LIGHTPEN VERSION ONLY	55
11.0 CADPAK TUTORIAL - KEYBOARD VERSION ONLY	63
12.0 CADPAK TUTORIAL #2 (BOTH VERSIONS)	71
13.0 CADPAK TUTORIAL #3 (BOTH VERSIONS)	73
14.0 TIPS ON USING CADPAK	77
14.1 DEFINING OBJECTS	77
14.2 DESIGNING FONTS	78
14.3 CURSORS	78
14.4 MAKING T-SHIRTS	79
APPENDIX A - COLOR NUMBER TABLE	81
APPENDIX B - PRINTERS / INTERFACES	82
APPENDIX C - 1351 MOUSE INSTRUCTIONS	91

1.0 WHAT IS CADPAK-64?

CADPAK-64 is a program for the Commodore-64 which helps you draw pictures and graphic designs easily and accurately. The pictures have a resolution of 320 points wide by 200 points high. When completed, the pictures are printed using a dot matrix printer in either a small or large size. The pictures may also be saved on diskette for later recall.

Unlike other drawing systems, CADPAK allows you to get an exactly scaled printer output on your dot matrix printer. It also allows you to operate in the units of your drawing problem (feet, miles, etc.) and all dimensions you see during the drawing process are those external dimensions. The scale factor is set up when the screen is initialized. The printer distortion is compensated for so that circles are printed as true circles.

There are three versions of CADPAK 64 included in this package. The first is a light pen version which uses a light pen for selection of functions and options, and uses the light pen in the drawing process. The second version operates without a light pen and uses the cursor control keys on the keyboard to move the drawing cursor on the screen. The third version uses the 1351 Mouse (see Appendix C for mouse instructions). Except for a few minor differences, these three versions are identical. (The light pen or mouse versions are better if your uses for CADPAK consist of a lot of freehand drawing and/or widely spaced points on the screen.)

All of the functions of the CADPAK program are selected from a master menu of functions.

You have two graphic screens to work with. A menu function permits copying areas from one screen to another. Copying may include rotation in 90 degree steps, upsizing in multiples and/or reflection of the image. This allows a final design or picture to be developed by copying sections from one or several other screens. Text in four sizes may be placed anywhere on the picture.

For even greater design capability, CADPAK includes an object management system of 16 x 16 pixel objects, which are designed on the screen. Up to 104 objects are available at a time. Once objects have been

defined, they can be saved onto disk and recalled for CADPAK drawing. When an object is to be displayed on the screen, it may be precisely positioned anywhere on the screen and its SIZE, ROTATION in 90 degree increments, and REFLECTION (mirror image) are easily and precisely controlled. The object editor is also used to develop type faces for special printing applications. The special font may be used for text on a drawing instead of one of the Commodore character sets.

You can use any of seven patterns to fill an area of the picture. A pattern editor is included to allow you to easily design your own 8x8 pixel fill patterns. Other sets of patterns can be created, saved on disk and recalled.

A "TRY AGAIN" function is provided which corrects any mistake. The picture on the screen is restored to the state it was immediately prior to the last main menu function selected.

The SIZE.PRГ (located on the reverse side of the diskette) is provided to configure CADPAK to your printer. Please see the section concerning printer setup (Section 5) before running CADPAK

2.0 WHAT'S INCLUDED IN THIS PACKAGE

Three versions of CADPAK-64 (Lightpen, 1351 mouse and keyboard versions)

Three tutorials which lead you step by step through many CADPAK capabilities.

A set of objects including electronic and math symbols.

Pictures for the tutorials.

A USA and states outline which you can use for making filled in maps, such as for sales territories.

3 special fonts for lettering - Old English, 3-D and Tech.

A SIZE.PRG (located on the reverse side of the diskette) to configure CADPAK to your printer. Please see the section concerning printer setup (Section 5) before running CADPAK

3.0 **HARDWARE REQUIRED**

Commodore 64 Computer

1541 Disk Drive or MSD disk drive

OPTIONAL 1351 Commodore mouse

OPTIONAL Good quality light pen (such as Madison Computer McPEN)

OPTIONAL Graphic printers (and interface if needed)

BLACK & WHITE Printers

Epson MX or FX

C. Itoh Prowriter 8510A

Commodore 1525 or MPS 801

Commodore 1526

Star Gemini series

Siemens PT88/89

Okidata Microline

Okimate 10

A special user port interface version of the EPSON printer module is also included allowing connection with only a cable.

COLOR Printers

Okimate 10

C. Itoh Prowriter 8510SC

See APPENDIX B - PRINTERS/INTERFACES for details of interfaces and secondary address options.

4.0 BEFORE GETTING STARTED

Because the three versions are so similar, this manual will use the terms "function selection" and "point setting" instead of detailed instructions about using the light pen or cursor control keys. (Please see Appendix C for 1351 mouse instructions.)

4.1 LIGHT PEN VERSION

In the light pen version, function selection means pointing the light pen at the word describing the function or option you want and pressing the CTRL key (twice to get off the main menu).

Setting a point using the drawing cursor means pointing the light pen at the screen, pressing and holding the CTRL key and moving the light pen to move the cursor to the position you want.

The **ACCUPOINT** feature provides precise positioning and is activated when you release the CTRL key. This is indicated by a light blue border on the screen. You can move the cursor one position in any direction by putting the light pen on one of the four borders and pressing the CTRL key. When you have finished moving the cursor to the position you want, put the light pen back on the main screen area (not the borders) and press the CTRL key. At this point the drawing cursor has been set on the point that you want to indicate to the computer.

4.2 KEYBOARD VERSION

In the keyboard version, function selection means keying the first two letters of the function name on the main menu or the first letter of the option you want on the option menu.

Setting a point means pressing the CTRL key to establish the drawing cursor in the center of the screen and using the cursor control key (with and without shift) to move the drawing cursor to the position you want. The drawing cursor moves in steps of 8 pixels at a time for speed.

The ACCUPOINT feature provides precise positioning. The Accupoint feature is activated by pressing the <RETURN> key after the drawing cursor has been moved with the cursor keys. The border turns light blue, and from that point onward the cursor keys are used to move the drawing cursor one pixel in any direction. When it is properly positioned, press the <RETURN> key again to lock it in place.

4.3 LIGHT PEN OPERATION

The light pen can sense its position only if the area of the tv or monitor screen is lighted. Therefore the normal drawing mode uses a white screen with black color for the lines. The screen border is light green so the light pen can properly sense when it is on the border. Some light pens may react differently to different colors (most light pens don't see red very well). A screen reverse function is provided to change colors on the entire screen. This allows generating a very dark picture by doing it with black lines on a white screen and then reversing the colors in the whole picture.

Light pen triggering is through the tip switch (if the light pen includes one) or by pressing the CTRL key. Throughout this manual we will call this "pressing the CTRL key". We will also refer to a press and release of the light pen tip switch or the CTRL key as "cycling the light pen".

4.4 SCREENS

At all times there is the BASIC screen (used for menus and keyed input) and one of the two graphic screens available. Press the F5 key to see the BASIC screen or the F7 key to switch to the graphic screen. Switching between these screens is automatically controlled by CADPAK, so you shouldn't have to use these keys except to "peek" at the graphic screen during menu selection. Cycling the light pen on the right border of the screen will also switch between the BASIC and graphic screens.

4.5 RESTART

The STOP key is disconnected to prevent accidental stopping of the program (since the STOP key is so near the CTRL key). If the program stops due to an error, type GOTO 999.

4.6 **COLORS**

The graphic screens are set up in '64 high-resolution mode which normally implies only two colors (black and white). However, ANY color can be used to draw on the screen. The only restriction is that only one drawing color can be used in each 8x8 pixel cell on the screen. If a second color is used in cell, all the points in the cell will show in the last drawing color. As long as there is an adequate amount of space between different color cells, many colors can be used on a screen. The table of colors and color numbers is included as APPENDIX A. Note that the first 8 colors correspond to the numbers on the keys.

4.7 **DRAWING MODES**

There are three modes for the drawing functions. The normal mode is WRITE which puts lines onto the screen. You may select ERASE mode which erases the points displayed, or RVS mode which switches each point. This shows the new drawing line by reversing the point were it is written over the original drawing. It is used when you want to see a line whether it goes over black or white areas. The default mode is WRITE.

4.8 POSITION

There are various ways you can position lines, boxes, etc, on the screen.

First, you select the function you want from the main menu, and select options under that function. After all the options have been selected, you will then have to move the drawing cursor on the screen to set the first point.

MOVE DRAWING CURSOR

In the light pen version, this is accomplished by pressing the light pen to the screen and pressing the CTRL key and holding it down. You may move the light pen anywhere on the screen and the cursor will follow the tip of the light pen until you release the CTRL key.

In the keyboard version, you must press the CTRL key to indicate to CADPAK 64 that you want to show the drawing cursor and move it (instead of the other point setting options below). When you release the CTRL key, the drawing cursor will appear in the center of the screen or on top of the last point you set. Use the cursor control keys (lower right corner of the keyboard) to move the cursor either down or to the right of its present position. Press and hold the SHIFT key, and use those cursor control keys to move the drawing cursor up or to the left of its present position. The cursor will move in steps of 8 pixels at a time to allow you to get to any area pretty quickly. When you are as close as you can get to the point you want, press the <RETURN> key.

The drawing cursor will probably not be exactly where you want it to be either because of the light pen accuracy or because the cursor keys move in 8 point steps. Hence, the Accupoint feature is automatically activated. The border of the screen will turn cyan (light blue). During Accupoint, the position of the cursor in your external dimensions is shown on the BASIC screen (press the F5 key). For a second point in a function (such as the second corner of a box), the change in x and y (DX, DY) is also shown, along with the straight-line distance (DIST) to the last point.

In the light pen version, to move the cursor up by one pixel, touch the light pen to the top border (cyan area) and press the tip or CTRL. To move the cursor one pixel to the sides or the bottom, do the same with the corresponding cyan border area. This step may be repeated as many times as necessary to precisely position the cursor. To exit Accupoint, put the light pen anywhere on the main screen area (NOT the cyan borders) and press the tip or CTRL key.

In the keyboard version, use the cursor keys to move the cursor as before, only now the cursor moves in 1 point steps. Press <RETURN> when it is where you want it. The border will change back to its normal color and the function will proceed.

The ZOOM and COPY BLOCK functions operate on groups of 64 pixels at a time (8x8 cells). With these functions, Accupoint moves the cursor 8 pixels at a time. Accupoint does not operate with the DRAW or RUBOUT functions.

KEY IN COORDINATES

You can specify a point by keying its coordinates in. Press the Commodore key (C=). This shows your dimensions, the x and y positions of the last point you entered, and asks you if the values to be keyed in are either absolute (A) or relative (R) to the last point. (A third option (L) is included which takes you back to lightpen input in case you press the C= key in error).

If you press A for absolute positioning, you are then asked to input the x and y coordinates of the point. Simply key these in as two numbers with a comma separating them in your external dimensions.

If you select the relative option (R), you are asked to key in the x and y change you want to make from the last point. Simply key in the values and press <RETURN>. The graphic screen is shown and the cursor is positioned at the point you specified.

DIVIDE MODE

The third option for point specification is the divide mode. This allows you to specify a point any fraction of the distance between two other points. The most frequent use is to put a point halfway between two other points. To use this, you do the following:

Press the left-arrow (<-) key. The border of the screen will turn purple to indicate that the divide mode is in effect. Now specify the first of the pair of points by using either the drawing cursor, or the Commodore key and the keyboard.

After you have set the first point, the screen border turns purple again, and now set the second point.

After the second point has been specified, you will see the X and Y coordinates of the first and second point to be used in the division. Then CADPAK prompts you with the word RATIO and shows ($1/2 = 1,2$). This means you are to enter the fraction but instead of using the normal /, put a comma between the numerator and denominator.

The system will compute the position of the new point using the fraction of the distance you specified, display its value and then move the cursor to the point on the screen. If you just press <RETURN>, the default ratio will be $1/2$ of the distance.

To help you know that CADPAK is expecting light pen or drawing cursor input, the '64 will make a tone.

If you want to turn all sound off (or back on again), go to the UTILITIES function and select SOUND.

4.9 DISK FILES

In order to separate the different types of files on disk (pictures, objects, and patterns), each has been designated with a unique prefix in the file name. All picture files are saved with a "P." as the first two letters, all object files are saved on disk with "O." as the first two letters, and all patterns are saved on disk with "Z." as the first two letters. These prefixes are automatically added to your filename if not already there whenever you READ or WRITE on disk.

4.10 DIRECTORY DISPLAY

A special directory display feature is included in CADPAK. This allows easy selection of a file to be used in a subsequent READ or SAVE command. When you select the DIRECTORY option at various places in the system, the size, and name of all files on disk OF THAT TYPE are shown, following an entry number along the left side of the screen. You may temporarily stop the display by pressing the space bar. Press the F5 key to resume the display. Key the entry number of the file you wish to select and press <RETURN> or key 0 (zero) to re-display the entire list. If you select a number larger than the largest shown, you will be returned to the CADPAK menu without selecting a file. The filename of the entry you selected is automatically available to the next READ or SAVE operation (including prefix). To see all entries on disk there is a ALL-DIRECTORY option in the DISK/SAVE/RESTORE function.

4.11 DISK DRIVE NUMBER

The normal (default) disk device is 8. To use another drive for objects, pictures, etc. go to the DISK/SAVE/RESTORE menu option and select the UNIT CHANGE option. The CADPAK diskette must be in device 8 when using the pattern editor. There is a reminder message when loading the pattern editor in case other diskettes are inserted into device 8.

4.12 FUNCTION KEYS

In addition to the F5 (BASIC screen) and F7 (graphic screen), function keys are used for:

- F1 Press this key to indicate end of text input (TEXT function). Press this key to return to main menu in the keyboard version.
- F2 (press and hold SHIFT and F1) - Light pen recalibrate. Use this at any time if you can't use the light pen to select the the LP ADJ menu option. The current graphic screen will be preserved.
- F3 Change cursor priority. Normally the many cursors on the screen are displayed IN FRONT of the drawing lines. Pressing F3 temporarily puts the cursors BEHIND the lines. Pressing it again will move them in front again. For a permanent change, go to the UTILITIES function, TARGET and the CURSOR PRIORITY option.
- F4 (press and hold SHIFT and F3) - TRY AGAIN! This key will erase the results of the last function and allow you to continue without having to go back to the main menu.

5.0 CADPAK SETUP (PRINTER DIMENSIONS)

While there are many programs which let you draw on the Commodore screen and make a printout of your drawing, CADPAK is the first program to allow precise **dimensioning** of the printouts. In addition, scale conversions are performed automatically so you can draw and specify things in real world dimensions and CADPAK converts these automatically to a properly scaled printout.

The maximum size and exact proportions of the printout will depend on your printer which is why a **sizing program** is included. The process takes only a few minutes and prepares both a small and a large size printout on your printer. You must measure the dimensions and then key them into the Commodore. CADPAK saves these on disk and reads them automatically whenever you run the CADPAK program. You will also notice that the ratios of the width to the height of the two sizes of printouts are different. Again, these are different depending on the printer. Whenever you start a drawing you must select either a small or large size printout. The dimensions you keyed in the sizing step are used by CADPAK in the scaling calculations. They are also used in modifying the circle so that it will be a true circle on the printout (even though it may be oval-shaped on the screen.) The only limitation of this method is that the dimensions will be correct only for the printout in the size you selected. You can print out your drawing in either size, but only the size you selected when you started the drawing will be correct. As a reminder, the size selection you made at the start of the drawing is indicated on the printout function option screen.

You may save a drawing to disk and bring it back again. The scaling will not be correct unless you clear the screen before recalling the drawing with the same printout size and dimension scaling as you had when you saved the picture.

It is probably easiest to understand with an example. Suppose you wanted to lay out a room which was 12 feet by 16 feet in size. You probably want a large size final printout, so select the large size when the screen is cleared. The default paper size will show: the width as 8.875 inches and the height as 6.6 inches (inside an 8 1/2 x 11 sheet of paper turned sideways). These are dimensions from an Epson FX-80 in the sizing step. Next, you enter the external dimensions as "feet". The next question is the number of feet per

inch to the drawing. Since our room is 16 feet long, and we want to fit it in inside an 8 3/4 inch paper, select 2 feet per inch. The next step is to go into CADPAK and draw the box to define the room. All that is necessary to do this is to select the box function. Press the C= key to allow you to key co-ordinates and then one corner will be at the coordinates 0,0 (feet) and the other corner will be at coordinates 16,12 (feet). The box will be drawn on the screen. From this point on the computer will automatically show you where you are in feet from the origin (lower left corner) whenever you move the lightpen on the screen. You can measure straight line distances in feet on the screen (even at angles) by using the MEASURE function. You can key in the positions of things, such as a table, and specify one corner of the table in feet from the walls and then specify the other corner of the table using relative foot measurements from the first point. You must use decimals, even with feet and inches.

Another place the dimensioning is incorporated is in the drawing cursors. Normally when you move the cursor on the screen a blue target is shown. There are four gray cursors located above and to the sides of the blue target. The distance between these gray cursors and the blue cursor is automatically set at either 1 inch or 1 centimeter on the paper. This can be changed by going to the cursor positioning screen (UTILITIES function). If you do so in the example above it will show the current cursor spacing at two feet because 2 feet is one printout inch. You can decrease this or increase this (in quarters of a foot) to provide a handy relative measurement around the cursor at all times on the screen.

5.1 SETTING THE DIMENSIONS FOR YOUR PRINTER

In order to adapt CADPAK exactly for your printer, you must run the following program steps. If you want to bypass this temporarily to run the demonstration you may. The distribution diskette has been set up for an Epson FX80 printer using inches as the dimensions.

The steps to adapt this to your printer are as follows:

- 1) Reset your Commodore 64 by turning the power off and then on again or type "SYS 64738".
- 2) Make sure your printer is attached to the system, turned on and READY. Insert the CADPAK distribution diskette UPSIDE DOWN into the disk drive. The "SIZE.PRG" is located on the reverse side of the distribution diskette.
- 3) Type LOAD"SIZE.PRG",8. This will load in the sizing program.
- 4) When the computer prompts READY, type RUN.
- 5) The SIZE.PRG is continually updated to include new printers, please follow the instructions displayed on the screen.

6.0 **LOADING CADPAK-64**

- 1) If you are using the lightpen, plug it into joystick port 1 on the right side of the '64.
- 2) Make sure your printer is connected to the '64, turned on and READY.
- 3) Reset the '64 by turning the power off and then on again or type "SYS 64738". The system will not load if the DOS wedge is active in the '64.
- 4) Insert the distribution diskette into the disk drive (#8).
- 5) For the light pen version, type LOAD "LP*",8 and press <RETURN>, or LOAD "LPCADPAK-64",8.
- 6) For the keyboard version, type LOAD "KB*",8 and press <RETURN>, or LOAD "KBCADPAK-64",8.
- 7) For the 1351 mouse version, type LOAD "MO*",8 and press <RETURN>, or LOAD "MOUSECADPAK-64",8.
- 8) When "READY." shows, type RUN and press <RETURN>. The Copyright will appear.
- 9) You are next asked for the printer type. Key the number which corresponds to your printer type and press <RETURN>. If you don't have a printer, select any of the numbers. The disk drive will run for about 65 seconds.

- 10) In the light pen version, the screen will turn white with two black squares in the center for light pen alignment. Place the light pen directly between the squares and press it (if it has a tip switch) or press the CTRL key. The light pen cursor consisting of a center target and 4 surrounding targets will appear and move toward the squares in the center as alignment takes place. Hold the light pen in that position until the screen changes. Then release the pen (or key).
- 11) The next prompt asks for the size of printout you wish to set up. Press either the S or L keys.
- 12) The next prompt asks you for the paper size in the dimensions you specified in the sizing program. The default sizes (measurements a and b you keyed in) are shown for the size you selected. If you wish to select these (the maximum size) simply press <RETURN> for the width and height prompts. If you want a smaller, specific size printout, key the height, press <RETURN> and key the width and press <RETURN>.
- 13) The graphics screen will be cleared and a black border will be shown around the screen in the size you specified.
- 14) The next prompt asks for the external dimensions you want to use. If you press <RETURN> (the default) it will be the same as the paper size dimensions. Here you may specify feet, miles, etc. Key the name. The next prompt asks how many of these per (inch or centimeter) on the paper. The default is one. Key the number and press <RETURN> or only press <RETURN> to accept the default (1). The main menu will appear.

7.0 CADPAK-64 MAIN MENU

The main menu lists 22 functions which can be selected.

In each of these functions, you can return to the main menu from any selection by moving the light pen to the right border of the screen and pressing the CTRL key or press F1 in the keyboard version.

The main menu also shows the screen number of the screen being displayed (SCREEN 1), the current drawing color number (COLOR 1) and the mode setting (WRITE, ERASE or RVS).

A reminder is shown at the bottom of the menu that you can input with the C= (Commodore key) or the <- key for divide. Also the name of the file in screen 2 is shown or the word "GRAPHIC" if you are using it as a second graphic screen (it's blank to start).

Again, function selection means:

(Lightpen version) - pointing the lightpen at the word describing the function or option you want and pressing the CTRL key twice.

(Keyboard version) - keying the first two letters of the function name on the main menu or the first letter of the option you want on the option menu.

For many functions, one or more option menus will appear before the function is executed. You select these in the same way, by cycling the light pen over your choice or by keying the FIRST LETTER in the keyboard version.

7.1 DRAW

FUNCTION - This function provides free-hand drawing of lines on the screen as long as the light pen is depressed. Although the drawing usually appears as a series of points, the points are actually connected by short lines so the FILL function will work properly.

LIGHT PEN OPERATION - Put light pen on screen at start point and press CTRL. Move light pen to end of line and release CTRL. The smoothness of the lines will depend on the precision of your light pen and how fast you move it. It can be improved by increasing the value of the smoothing control in the UTILITIES function, drawing cursor option and/or moving your hand slower.

KEYBOARD OPERATION - The keyboard version of the DRAW function is slightly different. The first step is to set the first point in the normal way (use the cursor control keys to move to the general area, press <RETURN>, and then use the cursor control keys to move to the specific starting point of the line you want to draw, then press <RETURN>. This sets the first point of the line.

Next, use the cursor control keys to move the drawing cursor one pixel at a time in any direction. When you get to the end of the first line segment, press the <RETURN> key to draw the line from the first point you set to this current point. Then use the cursor controls keys to move the cursor some more, press <RETURN> to draw the line, and so on. When you have drawn the last segment, press the F1 key to return to the main menu.

Although this is slightly more time-consuming than free hand drawing using the light pen, the results can be similar. The curve you are drawing will be connected so it can be filled without bleeding out of the area. If you need to go large distances for each segment, use the JOINTED option of the LINE function.

7.2 LINE

FUNCTION - This function draws lines by defining the endpoints.

OPTIONS - (TWO)

LINE TYPE

You can draw either a **SOLID** line or a **DASHED** line.

LINE SLOPE

JOINTED - This lets you draw a series of connected straight lines.

ANY - Lets you draw a line at any slope on the screen.

HORIZONTAL - This allows you to draw only horizontal lines.

VERTICAL - This forces the line to be vertical.

PARALLEL TO LAST - This constrains the line you are drawing to be parallel to the last line you drew.

RIGHT ANGLE - This draws a line at a right angle (perpendicular) to the last line drawn. (The angle on the screen may look odd because of the printer compensation, but it will be correct on the printout.)

OPERATION - The graphic screen is shown.

Set the first point of the line.

Set the point for the other end of the line.

The line will be drawn.

In the jointed option, the beginning of the second line will automatically be the end of the first. For all others, you must specify both ends of the next line. To go back to main menu, cycle the light pen on the right border or press F1.

7.3 RAYS

FUNCTION - This draws a series of straight lines from a starting point.

OPERATION - Set the first point (start point, common for all lines).

Set end point of first line.

The line will be drawn.

Set end point of second line or return to main menu.

7.4 BOX

FUNCTION - This function draws rectangular boxes on the screen.

OPERATION - Set point for one corner.

The other corners of the tentative box are shown by 3 red targets and moved by the drawing cursor.

Set point for opposite diagonal corner.

The box is drawn.

Set point for first corner of next box or return to main menu.

7.5 CIRCLE

FUNCTION - The circle function draws one or more circles with the same center. It is purposely distorted on the tv screen so the printout will be a true circle.

OPERATION - Set point for center of circle.

The left, top and bottom points of tentative circles of a radius equal to the distance of the drawing cursor from the center are shown.

Set radius by setting point at the 3 o'clock position.

The circle will be drawn.

Set point for second radius or return to main menu.

7.6 ELLIPSE(OVAL)

FUNCTION - An ellipse requires three points to specify it. The ellipse can be at any angle and any shape. Because of the large number of calculations involved after the second point is set, cursor positioning is slower than other functions.

OPERATION - Ellipses are specified as follows:

Set the point which is the end of the long dimension of the ellipse, (either end).

Set the point which is one side (short dimension) of the ellipse.

Set the center of the ellipse. As you position the center, cursors will mark the first two points and the other end of the long dimension of the ellipse.

The ellipse will be drawn.

Go back to main menu or step 1 above.

7.7 FILL

FUNCTION: - The fill function fills in an area, either in a solid color or a pattern from a set of pre-developed patterns on the screen or disk.

OPTIONS:

SOLID - fills in the area with the current drawing color.

Set a point inside the area to be filled.

The area will be filled with the proper color.

PATTERN - fills in the area with a selected pattern.

For the pattern option, another menu is shown. Select the USE option to use one of the patterns in memory. The other options are described after the operations.

OPERATION - Light Pen - The current set of seven patterns is shown on the right edge of the graphic screen. Select the one you want. Put the light pen over the desired one and cycle it. The patterns will be removed.

OPERATION - Keyboard - Use the cursor down and up key to move the marker up or down to the one you want. Press <RETURN> and the patterns will be removed.

The graphic screen is displayed. Set a drawing cursor at a point INSIDE the area to be filled.

If for some reason, you missed an enclosed area and the fill bleeds out to the whole screen or starts to fill an area you don't want, press the SPACE BAR to stop the fill operation. Then you can undo the bad filling by pressing the F4 key (SHIFT and F3). The graphic screen will be restored to the picture as it was prior to the fill function.

With patterns, the area will first be filled with solid color, then the pattern will be copied into the area.

OTHER PATTERN OPTIONS:

READ

The filename from the last disk or DIRECTORY command is shown. Press <RETURN> to read that file or key in another pattern file name and press <RETURN>. You will be returned to the main menu. Now select the fill pattern option and a new pattern will be shown.

DIRECTORY

The size, name and type of all pattern files on disk are shown, following an entry number along the left side of the screen. You may temporarily stop the display by pressing the space bar. Press the F5 key to resume the display. Key the entry

number of the file you wish to select and press <RETURN> or key 0 (zero) to re-display the entire list. If you key a number higher than the highest on the list, you will be returned to the options menu.

EDITOR

The current screen will be saved, and if the CADPAK disk is not in drive 8, the message "CADPAK DISK INTO DEV 8 - ANY KEY" will appear. Insert the disk and press any key. The pattern editor program will be read in from device 8. See the PATTERN EDITOR section for details on creating your own fill patterns.

7.8 TEXT

FUNCTION - This function permits writing text or graphics character strings on the screen in various sizes using either the standard Commodore characters or a special font. For a special font, it must be loaded into screen 2 BEFORE this can be used.

OPTIONS - Character Set

1. UC/(symbols) = Uppercase & Graphics
2. RV UC/(symbols) = Reversed Uppercase & Graphics
3. UC/LC = Upper & Lower Case
4. RV UC/LC = Reversed Upper & Lower Case
5. SPECIAL FONT

SIZE OPTION - [except special font]**Normal**

Height x 2 - Double height

Width x 2 - Double width

Large - Double height and width

OPERATION - Commodore fonts

Set point at upper left corner of the first character.

Type text. Use the <RETURN> key to go to a new line. Press the F1 key to exit back to the main menu. The DELETE key erases incorrect letters within a line. The two cursor control keys (CRSR) and with SHIFT on the keyboard will move the letter placement cursors around in one pixel increments. This is useful for super and subscripts.

Press F1 to exit and return to main menu.

OPERATION - Special fonts

If you have not loaded any thing into screen 2, the message "LOAD OBJ/FONT" will appear. Press any key and then use OBJECT/FONT MGR. option to load it.

Set point at lower left corner of 1st character.

Four size cursors will show minimum size.

Set point at upper right corner of first character to set size.

Type text. Use the <RETURN> key to go to a new line. Press HOME key to exit back to the main menu. The DELETE key erases only the last letter. The two cursor control keys [CRSR] and with SHIFT on the keyboard

will move the letter placement cursors around in one pixel increments. This is useful for super and subscripts.

7.9 ZOOM

FUNCTION - This function lets you "zoom in" on an area of the screen and see/change individual pixels. This permits fine adjustment of pictures, beyond the resolution of the light pen and tv systems.

OPERATION - Put drawing cursor at lower right corner of area to be zoomed. Four cursors outline the area.

When the point is set, the expanded area is shown. Use light pen to point to pixel to change (light pen version) or use cursor keys to move white pixel (keyboard version).

Edit the pixels by:

<- (left arrow)-force pixel OFF

C= (Commodore key) force pixel ON

CTRL key =flip pixel.

Move light pen or white dot to border to scroll.

Put light pen over EXIT word and cycle to exit, or press F1 in keyboard version.

7.10 USE OBJECTS

FUNCTION - This copies objects from the object workarea on screen 2 to your drawing.

OPTIONS:- See FIGURE A for comparison of the results of different options.

NORMAL - This copies an object in normal form to screen (you can control the size).

MIRROR - This copies an object with mirror reflection.

TURN - This copies an object with rotation.

OPERATION - You must create or load a set of objects. [Use the OBJECT/FONT MGR function]. Choose normal, mirror, or turn option.[This determines what happens when you move the light pen for the second point below, or to the left of the first point.]


The set of objects on screen 2 is shown and you use the light pen or cursor keys to move the target over the one you want. You are automatically returned to screen 1.

Set a point where you want the LOWER LEFT corner of the object to go.

Set a point where you want the upper right corner of the original object to be. This also sets the sizing in increments of 16 pixels in the x, y, or both directions. The object is copied to the screen.

Another copy of the same object may be made without having to re-select it by simply setting the point for the lower left corner of the next copy.

FIGURE A



7.11 RUBOUT

FUNCTION - This function works like an eraser on a pencil. When pressed, the light pen erases 8x8 areas.

OPERATION - LIGHT PEN - Put the light pen where you want to erase and press CTRL.

Use the right border and cycle the light pen to return to the main menu.

OPERATION - KEYBOARD - Move cursor to first position to be erased. (Will erase upper right cell from drawing cursor).

Press <RETURN> to erase the point.

Move cursor to next point and press <RETURN>.

Press F1 to return to main menu.

7.12 POINTS

FUNCTION - You can place single dots or a spray of dots on the screen using this function.

OPTIONS:

SINGLE POINT - This option places a single dot on the screen.

OPERATION - Set point

Point is drawn

Set next point or go to main menu

SPRAY - (Light Pen Only) - This is like the DRAW function only it sprays a series of single dots as long as the CTRL key is held down.

OPERATION - Put the lightpen on the screen where you want to start.

Press the CTRL key to start spray.

Move lightpen to direct spray of points.

Release CTRL key to stop.

Place pen on right border to return to main menu.

7.13 ARC

FUNCTION - This allows you to draw a smooth curve between two points. The curve is actually a segment of an ellipse, and one end of the major axis (long axis) touches one of the two points.

OPERATION - Set the one end point of the arc.

Set the point at the other end of the arc.

Specify the center of the ellipse you wish. NOTE: The closer you move the center to the line between the two ends, the flatter the curve between the ends will be. The closer the center is to one of the end points, the smoother will be the curvature around that end point.

After the third point has been set, the arc will be drawn.

7.14 MEASURE

FUNCTION - This function operates just like a box, the only difference is that after the second point has been specified, the graphic screen is not changed, but instead the distances are shown on the BASIC screen. This is used primarily to measure straight line distances between points on the screen. It is useful because the distance is computed in your external dimensions.

OPERATION - Set point at one end of the distance to be measured.

The other corners of a box are shown by 3 red targets and moved by the drawing cursor.

Set point for the other end of the distance to be measured..

The coordinates of the second point are shown along with the x distance (DX) the y distance (DY) and the straight line distance between the points.

Set point for the 1st point of the next distance or return to main menu.

7.15 CLEAR

FUNCTION - This function clears the current display screen and sets up the screen colors and screen dimensions for drawing.

OPTIONS:

- 1) **YES** - Continue to clear the screen and erase anything on it.

2) **NO** - Returns you to the main menu.

OPERATION - Light Pen - You must choose the writing color. Note that there are 16 color choices (the cyan box is there but doesn't show against the background. Put the light pen under the box for the color desired (on the row with PEN- > and trigger it. A block of the selected color and the color number (see keys and table) are shown around the PEN ->. Cycle the pen at the right border if you don't want to change the color shown.

Select the background (screen) color the same way.

You must specify the printout size, width, height and dimensions, as when you startup the system.

OPERATION - Keyboard - The 16 color choices are shown. Key the color number of the drawing color and press <RETURN>.

Key the color number of the background color and press <RETURN>.

Specify the printout size, width, height, and dimensions as when you start up the system.

7.16 TRY AGAIN!

FUNCTION - This function fixes all your mistakes and problems with the most recently executed function. It "erases" the results of the last graphic function (all steps since last main menu).

OPERATION - The graphic screen is restored.

7.17 UTILITIES

FUNCTION - These utilities help you manage the light pen, drawing cursors, drawing colors, etc.

OPTIONS:

COLOR/MODE

This option allows you to select the color and mode to be used for drawing.

OPERATION - LIGHT PEN : Note that there are 16 color choices (the cyan box is there but doesn't show against the background. Put the light pen under the box for the color desired (under the row with PEN- > and trigger it. A block of the selected color and the color number (see keys and table) are shown around the PEN - >. Cycle the pen on the right border if you don't want to change the color shown. When you return to the main menu, the color number is shown next to COLOR in the upper right corner.

The mode select function allows you to select the mode for the plotting functions (BOX, LINE, CIRCLE, etc). The normal mode is WRITE which moves the points to the screen. You may select ERASE mode which erases the points displayed, or RVS mode which switches each point (exclusive-or). The default mode is WRITE. Place the light pen over the mode you want and cycle it. Note that the mode is shown on the main menu in the upper right corner.

OPERATION - Keyboard : Another list of options is shown:

CHANGE COLOR- Selects drawing color like screen clear

WRITE - Select write mode

ERASE - Select erase mode

RVS - Select RVS mode

DRAWING CURSOR

OPTIONS - This option lets you control the drawing cursor.

CALIBRATE [Light Pen only] - This option goes through the same calibration process as at program startup. Before doing the alignment, the current graphic screen is saved.

(CURSOR) SPACING

FUNCTION - This option lets you adjust the spacing of the four gray cursors used with the light pen on the screen. The initial spacing is the external dimension for 1 inch or 1 CM on the printout.

For example, if you want a number of lines spaced 2 feet apart, set this spacing for that amount. Then use the side cursors to position the pen cursor that far away from the last.

OPERATION-LIGHTPEN - The dimensions are shown at the top of the screen.

Place the lightpen over the + or - to increase or decrease the spacing.

Place lightpen on right border to return to main menu.

OPERATION-KEYBOARD - The dimensions are shown at the top of the screen.

Press the I or D key to increase or decrease the spacing.

Press F1 to return to main menu.

(CURSOR) PRIORITY

FUNCTION - Normally the many cursors on the screen are displayed IN FRONT of the lines. This function permanently puts the cursors BEHIND the lines. Pressing it again will move them in front again. For a temporary change, press the F3 key.

SMOOTHING [Light Pen Only]

This option lets you control the light pen responsiveness. Because light pens have some "jitter", especially in the horizontal direction, CADPAK-64 reads the light pen twice every time and compares the second reading to the first and selects the x and y values closest to the last ones used. Even with this double reading, some light pens give erratic readings. The smoothing function lets you force the system to take additional pairs of readings and average the results. Of course, additional readings will slow down the response of the system. The current setting (1 at first) is shown in the middle of the screen. Put the light pen over the word and trigger it.

REVERSE SCRIN (SCREEN)

FUNCTION - This function allows you to reverse the colors on the screen. It switches the

background and foreground colors in each screen cell.

SOUND

FUNCTION - This option toggles the sound on and off.

7.18 COPY [AREA]

FUNCTION - This function lets you take a rectangular area of one screen and copy it to another area on the same screen or the other graphic screen.

The copy function operates in one of two modes. The first mode is the block mode. It operates using 8x8 cells of the screen and allows you to copy a section of the screen, including color, to the same screen or to another screen.

The second mode is point mode. The point mode allows you to copy any rectangular area, and also has the advantage that when you copy it back, you can change its size, turn or mirror image it.

When this function is selected, you must also choose the EXTRACT or COPY IN functions. The EXTRACT is the one which copies the picture area to the save area in the computer. The COPY IN option copies the save area to the screen (you may swap screens in between these steps to copy images from one screen to another).

OPTIONS:

EXTR-BLK [Extract Block]

OPERATION - Set point at one corner of area to be copied.

Set point at opposite diagonal corner.

Area is copied to save area and you are returned to main menu.

NOTE-Due to memory limitation, you cannot copy more than 90% of the screen at a time. If the area you selected exceeds this limit, you will get the message "TOO BIG-any key". Press any key and then define a smaller area. It may be necessary to copy a picture in two parts.

COPY IN-BLK

FUNCTION - This option moves the save area to the current screen.

OPTIONS:

REPLACE - The image is moved into the screen (overlying anything in the area before).

COMBINE - The image is added to the screen area, adding to the points already turned on, but not deleting any other on-points.

GHOST - This shows the new pattern, as a "ghost" on the old screen. This option can also be used to erase a copy pattern by displaying it a second time (it reverses itself).

MATCH - This option leaves only those points which exactly match in the two images.

MOVE COLOR & IMAGE - This option moves both the image and the associated color to the screen. This would normally be used with the **REPLACE** option above.

IMAGE ONLY - This option moves the image but not the color information. Therefore the image will take on the colors of the new area. **COMBINE, GHOST AND MATCH** are normally used with the options above.

OPERATION - Set point at the **LOWER RIGHT** corner of the area where the saved image is to go.

The image is copied and the cursors will show the other corners where the area will be copied into.

For another copy, repeat above steps or go to mainmenu.

PT EXTR (Point Extract)

FUNCTION - To use this function specify the two corners of the rectangular area to be copied as with the box.

OPERATION - Set point for one corner

Set point at opposite diagonal corner.

The border of the screen turns red to indicate that the computer is copying the pixels to the save area. For large areas it takes some time.

You are returned to main menu.

MIRROR COPY IN-PT &

TURN COPY IN-PT

FUNCTION - These are the two copy back functions for the point mode. The only difference between the two is that the turn option allows the image to be

rotated in 90 degree increments and the mirror option instead makes mirror images in either the horizontal, vertical, or both directions.

OPERATION - Set the point where the LOWER LEFT corner OF THE ORIGINAL IMAGE is to go.

Set point where upper right corner of original should be. If no rotation or reflection is desired, simply move the light pen to the UPPER RIGHT the amount desired to scale the copy back image in its x and y dimensions. NOTE that the scaling is only done in integer multiples of the original size. After the second point is set, the image is copied to the screen. If you want to rotate or reflect the image, move the second point to the left or below the first point and the image will be rotated and sized in the same way.

The image is combined with the screen image.

You can make a second copy by simply positioning the light pen at the lower left of the area where you want the second copy to be.

7.19 DISK/SAVE/RESTORE

FUNCTION - This function selects whether the current screen is to be written to disk, if an image is to be read from disk or if other disk utility functions are to be performed:

OPTIONS:

NEW - This option lets you initialize a disk, WHICH WILL ERASE EVERYTHING ON IT - BE CAREFUL! You will have to key in the disk name (up to 16 characters) and press <RETURN>. Then

you will be asked for a two character identification. Key it and press <RETURN>. There will be some noise from the disk drive. The process will take about 3 minutes.

FILE SCRATCH - This option lets you erase a single file from disk. The filename can be keyed in or selected from a directory function before this option.

VALIDATE - This option performs the disk validate function, checking the disk directory and Block Availability Map. Most important, Validate removes any incompletely written files from the diskette (those with an * in the directory listing).

UNIT CHANGE [DEV] - This option is used to select another disk drive for all disk operations except program loading. Key in the new drive number and press <RETURN>. The default is drive 8.

ALL-DIRECTORY - This shows the complete directory of the disk (all types of files).

CHANGE NAME - This lets you rename a file on disk. The filename from the last disk or directory is shown. The the prompt "NEW=OLD". Key the new filename, then an "=" and then the present name of the file you wish to change.

SAVE - This option saves the current picture screen to disk. The filename of the most recently executed disk command is shown. You must key in a different filename or press <RETURN> to accept the one shown. Note-to replace a picture file on disk, use a SCRATCH, then SAVE.

DIRECTORY - This option displays the directory of all picture files on disk (P.) and makes the selected filename available to the next disk operation.

RESTORE - This option restores a picture from disk to the screen. The filename from the last disk operation (usually DIRECTORY) is shown. Press <RETURN> to use the name shown or key a different name and press <RETURN>.

If any disk drive errors occur, they will be displayed on the screen.

7.20 SWAP [SCREENS]

FUNCTION - This function moves the current screen to its save area in memory (not disk) and moves the other screen to the display.

7.21 OBJECT/FONT MGR

FUNCTION - Objects and Fonts are 16 x 16 pixel images. The second screen area of CADPAK is used to hold and manipulate these objects so they can be copied into screen 1 easily in the TEXT or USE OBJECTS functions. There are a total of 104 objects per screenful. Underneath each object is its key letter designation (this is used when designing fonts).

Manipulation of the two screens is completely automatic. The first step is to read an object file in from disk or create it using this function. Objects are stored in the same format as a picture image, only the file prefix is "O." instead of "P." This object "picture" is read into screen 2. If you happen to be on screen 2 when you select the READ or OBJECT functions, you are reminded of this fact and you have three options:

- 1) To scratch (ignore) whatever you had on screen 2.
- 2) To copy whatever you have on screen 2 to screen 1 and continue.
- 3) To save whatever you have on screen 2 to disk as an object file ("O." prefix).

The object/font image is read into screen 2.

OPTIONS:

READ - This option reads a set of objects from disk.

OPERATION - The filename from the last disk or directory command is shown. Key in another name or press <RETURN> to use the one shown.

DIRECTORY - The filenames of all objects files ("O." prefix) on the disk will be shown.

OPERATION - Select the number corresponding to the set of objects file you want and press <RETURN>.

EDITOR - The objects are created and changed through the object editor. The object editor allows you to completely clear an object screen and/or to select which object you want to change.

OPTIONS:

MODIFY - This option lets you modify one or more objects.

OPERATION -Light Pen - The current set of objects is shown.

Place the lightpen over the one you want to change and cycle the lightpen. The object selected is shown in a zoom format and it is edited using the same control keys (left-arrow for erase, CTRL for flip the point, and Commodore key to force a point on.) When all changes to an object are completed, use the right border of the screen to get back to the complete set of objects and then another object may be selected or using the right border of that screen you will return to the object menu.

OPERATION - Keyboard - The current set of objects is shown.

A blue cursor is shown in the middle of the screen. Use the cursor control keys to move it over object you wish to change and press <RETURN>.

The object is shown in ZOOM format with a white dot near center. Use cursor keys to move the white dot around. Use left arrow to force point off, C= to force it on and CTRL to flip point.

Press <RETURN> to select next object.

READ - You will be asked for the filename of the set of objects to read. These will be read into memory and then you will be returned to this object editor menu.

DIRECTORY - The filenames of all objects files ("O." prefix) on the disk will be shown. Select the number corresponding to the set of objects file you want and press <RETURN>.

SAVE - The current set of objects is written to disk under the filename you select.

CLEAR - This option completely resets and clears out the object workarea.

7.22 PRINT

FUNCTION - This function initiates the printing of the current screen.

OPTIONS:

SMALL - This will give printout approx 1/4 of an 8-1/2 x 11 inch sheet.

LARGE - This will print the screen approx full size (8-1/2 x 11 inch sheet).

The size you chose when the screen was cleared is marked by a ">". If you don't select the same size, the dimensions will not be correct.

Ready the printer and select your choice of size. To abort the printout, press the SPACE BAR.

See APPENDIX B - PRINTERS/INTERFACES for secondary addresses, etc. for various printers and interfaces.

8.0 CONFLICTS

The DISK I/O function, the FILL (pattern only), DIRECTORY, COPY, USE OBJECT and SPECIAL FONT functions all share the same workspace. This means that you cannot copy an area out of one screen, load another screen in from disk and still have the copied area available. Likewise a pattern fill will overwrite the COPY AREA function.

...

...

...

...

...

9.0 PATTERN EDITOR

At any one time there are 7 patterns which may be selected in the FILL function. The set of patterns may be changed. Each set of patterns is stored as a small program file on disk. The standard pattern set loaded when CADPAK is started has the name "Z.FILL.P". From the pattern option of the FILL function you can select the pattern editor program. This will be loaded from device 8 (the CADPAK disk must be in the drive).

Each pattern is made of an 8x8 set of dots (pixels). Each of the 64 pixels can either be on or off. In order to see how adjacent rows and columns of the same pattern fit together, four patterns are displayed together when you select them during this editing process. Only the lower right pattern is active. The other ones are automatically made to be identical copies of it.

9.1 PATTERN EDITOR MENU:

MODIFY

This option allows you to select one of the seven patterns and edit it using the same kind of technique as with the zoom function, as follows:

The screen is cleared and the seven patterns are shown at the right hand side of the screen. Place the light pen over the pattern you want to change and cycle the light pen, or use the cursor up/down keys to move in the KB version. The pattern will be presented to you in zoom format. Place the light pen over the pixel in the lower right corner that you wish to change and press the CTRL key to flip that pixel (if its on turn it off, if it's off turn it on), press the left-arrow key to turn off the pixel or press the Commodore key to turn the pixel on. Do the same with other pixels in the pattern to achieve the pattern

you wish. When finished, use the right hand border of the screen to get back to the pattern editor menu.

READ

This option allows you to read in a pattern file from diskette. Simply key in the pattern file name.

DIRECTORY

This option lets you display the directory of all pattern files on the diskette drive, and lets you select the one you want for the next READ or SAVE.

SAVE

This option lets you save the pattern file to diskette. Simply key the file name (up to 14 characters) and it will be saved on disk with an automatically added Z. prefix.

CLEAR

This option lets you completely clear out a single pattern so you can create a new one. After the pattern is cleared, proceed to create the new one as with the MODIFY function above.

To return to the CADPAK main program, use:

RIGHT BORDER- Lightpen version

F1 KEY - Keyboard version

The CADPAK program will be read and the screens will be restored.

10.0 CADPAK TUTORIAL-LIGHTPEN VERSION ONLY

The easiest way to learn is by doing. This tutorial will acquaint you with many of the functions of CADPAK.

STARTUP

First, load "LPCADPAK-64" into the computer (See LOADING CADPAK).

Make sure the light pen is plugged into CONTROL PORT 1 (on the right side).

You should see the alignment screen and hear the tone. Place the light pen over the two squares in the center and press it (or the CTRL key if light pen doesn't have switch built in). While you hold the key the five cursors will appear and move toward the two squares in the center. When they are exactly over the center, the screen will change.

The next prompt asks you which size printout you desire, small or large. (You can select the either size at print time but circles may be distorted and the dimensions will be wrong unless it is the same one you select at this prompt.) For this demonstration select S for small. The next prompt shows you the paper size dimensions you selected during the sizing programs (inches or centimeters). It shows the width of the small size you measured. To select that size, simply press <RETURN> to accept the default value shown. If you wish to change it to some other smaller size, key the size here and press <RETURN>. Next, you get a chance to adjust the height. Again, the value you entered in the sizing program is shown. If you wish to change it, key the value, otherwise press <RETURN>. At this point the screen is initialized and a box put around the area of the width and height you just specified.

The next prompt asks you for the external dimensions. The numbers above refer to the paper size and the size the image will be when printed. Now you get a chance to tell the computer the dimensions you want to work in and also give it the scaling factor to use. You can simply default to the same CM or inches size you selected above. Or, for example, you might choose to represent a twenty foot room on a five inch width piece of paper. In this case, your external dimensions would be feet, and so you simply key the word FEET at this prompt and press <RETURN>. The next question is the number per inch. In this example you would key four (feet) per inch. Now everything that you do in this drawing could be based on the foot measurements and not the inches. See the CADPAK SETUP section.

For this example, simply press <RETURN> to accept the default (1 INCH=1 INCH).

LIGHTPEN TESTING

To get a feel of the light pen, put it over the word DRAW on the screen and cycle it. The word DRAW marked with a ">". (If not, try moving the pen slightly up or down. If that doesn't help, try adjusting the sensitivity of the pen or the brightness of the screen.) When the ">" is shown, cycling the pen again at the same word will select the function. If the pen is not at the same place, the main menu will be redisplayed.

DRAW

We want to select the DRAW function, so after the second cycle over the word DRAW, the graphic screen (white with green border) will be displayed. This is what you write on. Put the pen at the screen to write your name. To write, press the switch or CTRL. To skip over an area, release the pen or switch. Write your first name about 1/4 of the size of the screen in the center. This will also show you how stable your light pen is. To make the light pen

less jittery, go to the smoothing adjustment in the UTILITIES function. To get there, put the pen on the right border of the screen and cycle it. The main menu reappears. Place the pen over the UTILITIES words (middle left) and cycle twice. Then put pen over DRAWING CURSOR words and cycle it. Then put the pen over the SMOOTHING word and cycle. The current smoothing value (1) will be shown in the center of the screen. Increase it by placing the pen over the + or lower the value by placing the pen over the - and cycling it. If the line from your pen was jittery, try increasing the value to four. Return to the main menu by placing the pen over the right border and cycling it.

Now view the screen (cycle pen at the right border of main menu or press the F7 key). You should see what you wrote before. Let's erase and try again with new smoothing. Go back to main menu (cycle pen on right border). Select CLEAR option (cycle twice). The color selection screen will be shown. Select the dark blue foreground color by placing the pen under the dark blue block and cycling it. You will see the block next to the word PEN change color. Keep the pen cycled until the block turns blue and the number 7 appears to the left. Then release the pen and the next color to be selected is the background (screen) color. Keep it white. You will have to select size again. Press S and accept all defaults. You will be returned to the main menu. Note that the pen color you selected (COLOR 7) is shown in the upper right corner of the main menu. Select DRAW again and write your name. If you set the weighting factor large (over 8) the pen response will be sluggish, but very precise.

BOX

Go back to the main menu. Select the BOX option to enclose your name. When the screen appears, press the pen to the place where you want one corner to go, say lower left. Press the pen to the screen and the five cursors which were at the alignment screen reappear (You can

adjust the distance them on the LP ADJ function. They can help align points some distance apart quite accurately.) When you release the pen switch the border will turn cyan (light blue). This is the ACCUPOINT function. To see it work, place the pen on the left border (cyan area) and cycle the pen. The cursors all move one pixel to the left. In the same way, you can move it up, down or to the right, point by point. You can see the actual x and y coordinates by pressing the F5 key. When the cursor is exactly where you want it, put the pen on the main screen area and press it. The border will turn green to let you know the ACCUPOINT feature is released.

Now move the pen to the other corner of the box on the screen and a lot of things move too! First the main cursor and the four surrounding ones always follow the light pen. There is a red cursor at the corner of the box you just set. Then there are two other red cursors which show where the other two corners of the box are. They move to show you where the box will be drawn. When you cycle the light pen next, you will be setting the box by fixing its other diagonal corner. Press the switch and ACCUPOINT is activated. Use it to position the corner exactly where you want it. Note that the other two corners move to stay coordinated. When you press the pen on the main screen, you exit ACCUPOINT and the box is drawn.

TRY AGAIN!

To see how the last function can be erased, go to the main menu (right border and cycle). Select the TRY AGAIN! function (cycle 2 times). If you now view the screen you will see it erased the box only, not your name. The TRY AGAIN can also be done while you are drawing on the screen in MOST functions by pressing F4 (SHIFT and F3).

CIRCLE

Let's put a circle around your name instead. Select the CIRCLE function from the main menu. The first point to define is the center. Put the pen in the center of your name and cycle it. ACCUPOINT will be activated, but if you keep the pen on the main screen (not border) and press the pen, you will bypass ACCUPOINT. Now put the pen at the approximate 3 o'clock position on the circle. You will see three red cursors moving to show the 12, 6 and 9 o'clock positions of the circle. When you cycle the pen, ACCUPOINT will be activated and you can precisely set the circle size. When you exit ACCUPOINT, the circle will be drawn. To draw another with the same center, simply put the light pen at the new radius and press it to start the process over. To quit drawing circles, put the pen on the right border and cycle the pen.

LINE

The LINE function operates similar to the BOX in that you must define with the light pen the two points for the two ends of the line. Before you get a chance to specify the end points of a line, you must select the line type (either solid or dashed). You must also select whether a line can have any slope (drawn in any direction on the screen) or if you wish the line to have either horizontal, vertical, or a slope parallel or at right angles to the last line you drew. After you select these options, then use the light pen, cursor, and ACCUPOINT, the same as with the box.

RAYS

The RAYS function operates in a similar fashion. The cursor is shown, then ACCUPOINT, then the line is drawn. Use the right border to exit.

Try LINE, RAYS, and CIRCLES now. Use the TRY AGAIN! function or the F4 key to erase your mistakes. It

restores the screen to the last FUNCTION. If you drew three circles after coming from the main menu, the TRY AGAIN will erase all three. When you have to draw a number of copies of the same shape, go back to the main menu after a few, so they will be saved in case the last one is bad.

CALL UP SAVED PICTURES

Now let's get down to a real drawing. Clear the screen, setting the foreground color to black and the background to white. Load in the starting space shuttle picture. Use the light pen to select DISK/SAVE/RESTORE. Select the DIRECTORY option. The list of all picture filenames on disk will show. Key the number corresponding to "P.START SHUTTLE". You will be returned to the disk option menu. Select the RESTORE option. The filename "P.START SHUTTLE" will appear. Since you want this, press <RETURN>. In about 30 seconds the picture will be loaded. (See it by cycling the pen on the right border of the main menu). Since we will want to add some other drawings to the shuttle picture, we must get them into the computer on the other screen. Do this by SWAP SCREENS (the new one should be blank with a green border). Now go to the DISK/SAVE/RESTORE function, read the DIRECTORY and RESTORE the picture called "P.TUTOR PARTS".

Use the right border to view the images from TUTOR PARTS (a moon and star).

COPY IMAGES

Copy the moon as follows:

Select the COPY function from the main menu and then the EXTR-BLK (extract block) option. Use the light pen just as you did in the box. When the second corner is placed you are returned to the main menu. To try the copy back, select COPY and then COPY IN-BLK option. Select

COMBINE and then IMAGE ONLY. Now the light pen is the BOTTOM RIGHT corner of the image. Move the pen around until its where you want (on a clear area of the TUTOR PARTS image). When cycled, the moon image will be copied. Move the pen to another area on the screen and cycle it to write another copy. Press the F4 to erase these copies, and then cycle the pen on right border to exit. Now SWAP and use the COPY IN-BLK to place the moon on the shuttle picture (upper left corner). SWAP to go back extract the star and then put several stars on the shuttle picture.

OBJECTS

Now add an object:

The Object function is one of the most powerful in CADPAK. In addition to being somewhat like the COPY function where one copy can be copied into another area, it permits sizing and rotations and precise positioning. Each object must be defined as a 16 x 16 pixel image in the OBJECT EDITOR. For now, call up a set of objects from disk as follows. Put the pen over the OBJECT/FONT MGR function and press twice. Then put pen over DIRECTORY and cycle. Key in the number corresponding to "O.TUTOR OBJECTS" and press <RETURN>. The name selected will be shown for you to confirm by pressing <RETURN>. The set of objects will be read in. You will be returned to the main menu. Select the USE OBJECTS function. Select the NORM option. To put one on the screen, place the light pen over the one you want (the satellite in the upper left corner) and press and hold the CTRL key. Release the key. The regular graphic screen will show. Press the light pen to the screen and put the pen where you want the LOWER LEFT corner of the object to go. ACCUPOINT will position it precisely. Then use the light pen to position the upper right corner. Cycle the pen to set the size. The F4 key will correct a mistake and you can draw another copy of the object without going back to the main menu.

FILL

Complete the shuttle picture by using the FILL function filling the lower nose area, the wing, the engines with solid color. Fill the earth with another fill pattern down and put a box around the title. You can fill the whole picture with the first fill pattern.

PRINT

Print the picture out by selecting the PRINT function. Then select either the small or large picture.

11.0 CADPAK TUTORIAL- KEYBOARD VERSION ONLY

The easiest way to learn is by doing. This tutorial will acquaint you with many of the functions of CADPAK.

STARTUP

First, load "KBCADPAK-64" into the computer (See LOADING CADPAK).

The first prompt asks you which size printout you desire, small or large. (You can select the either size at print time but circles may be distorted and the dimensions will be wrong unless it is the same one you select at this prompt.) For this demonstration select S for small. The next prompt shows you the paper size dimensions you selected during the sizing programs (inches or centimeters). It shows the width of the small size you measured. To select that size, simply press <RETURN> to accept the default value shown. If you wish to change it to some other smaller size, key the size here and press <RETURN>. Next, you get a chance to adjust the height. Again, the value you entered in the sizing program is shown. If you wish to change it, key the value, otherwise press <RETURN>. At this point the screen is initialized and a box put around the area of the width and height you just specified.

The next prompt asks you for the external dimensions. The numbers above refer to the paper size and the size the image will be when printed. Now you get a chance to tell the computer the dimensions you want to work in and also give it the scaling factor to use. (You can simply default to the same CM or inches size you selected above. Or, for example, you might choose to represent a twenty foot room on a five inch width piece of paper. In this case, your external dimensions would be feet, and so you simply key the word FEET at this prompt and press <RETURN>. The next question is the number per inch. In this example

you would key four (feet) per inch. Now everything that you do in this drawing could be based on the foot measurements and not the inches. See the CADPAK SETUP section.

For this example, simply press <RETURN> to accept the default (1 INCH=1 INCH).

To get a feel of the way CADPAK works, try something you're familiar with putting text on the screen:

Go to the TEXT function by keying "TE". You should see the menu with the font selections (1= UP/GR, 2=RV UP/GR etc). Press 3 to select the Upper/lower case option.

The next menu shows the size options. Press H to select height x2.

Press the CTRL key. The blue cursor appears near the center of the screen, surrounded by 4 gray ones. Press and hold the SHIFT key and press the left/right cursor control key (lower right of the keyboard) to move all 5 cursors to the left (to about halfway from the left edge).

Press the <RETURN> key and do this again and notice how the cursors move only 1 position at a time. This is ACCUPOINT mode.

Press <RETURN> to set the cursors for text.

Now type your name, using the SHIFT key for capital letters (like a typewriter).

When you have finished, press the F1 key to go back to the main menu.

BOX

Go back to the main menu. Select the BOX option (key BO) to enclose your name. When the screen appears, press CTRL to move the cursor to the place where you want one corner to go, say lower left. The five cursors which were at the alignment screen reappear (You can adjust the distance between them on the DRAWING CURSOR function. They can help align points some distance apart quite accurately.) When you press <RETURN> the border will turn cyan (light blue). This is the ACCUPOINT function. The cursors all move one pixel at a time. You can see the actual x and y coordinates by pressing the F5 key. When the cursor is exactly where you want it, press <RETURN>. The border will turn green to let you know the ACCUPOINT feature is released.

Now press CTRL. It seems nothing changes, (but that's because the cursors are on top of each other). Use the cursor control keys to move the drawing cursor to the other corner of the box on the screen and a lot of things move too! First the main cursor and the four surrounding ones always follow your commands. There is a red cursor at the corner of the box you just set. Then there are two other red cursors which show where the other two corners of the box are. They move to show you where the box will be drawn. When you press <RETURN> next, you will be setting the box by fixing its other diagonal corner. ACCUPOINT is activated. Use it to position the corner exactly where you want it. Note that the other two corners move to stay coordinated. When you press <RETURN> again, you exit ACCUPOINT and the box is drawn.

TRY AGAIN!

To see how the last function can be erased, go to the main menu by pressing F1. Select the TRY AGAIN! function by keying TR. If you now view the screen you will see it erased the box only, not your name. The TRY AGAIN can

also be done while you are drawing on the screen in MOST functions by pressing F4 (SHIFT and F3).

CIRCLE

Let's put a circle around your name instead. Select the CIRCLE function from the main menu by pressing CI. The first point to define is the center. Press CTRL and put the cursor in the center of your name and cycle it (notice how the gray side cursors help center it). ACCUPOINT will be activated, but just press <RETURN>, you will bypass ACCUPOINT. Now press CTRL and put the cursor at the approximate 3 o'clock position on the circle. You will see three red cursors moving to show the 12, 6 and 9 o'clock positions of the circle. When you press <RETURN>, ACCUPOINT will be activated and you can precisely set the circle size. When you exit ACCUPOINT by pressing <RETURN>, the circle will be drawn. To draw another with the same center, simply press CTRL and move the cursor to the new radius. To quit drawing circles, press <RETURN>.

LINE

The LINE function operates similar to the BOX in that you must define with the cursor the two points for the two ends of the line. Press LI and before you get a chance to specify the end points of a line, you must select the line type (either solid or dashed). You must also select whether a line can have any slope (drawn in any direction on the screen) or if you wish the line to have be either horizontal, vertical, or a slope parallel or right angles to the last line you drew. After you select these options, then use the cursor keys and <RETURN> key, and ACCUPOINT, the same as with the box.

RAYS

The RAYS function operates in a similar fashion. The cursor is shown, then ACCUPOINT, then the line is drawn. Use the F1 key to exit.

Try LINE, RAYS, and CIRCLES now. Use the TRY AGAIN! function or the F4 key to erase your mistakes. It restores the screen to the last FUNCTION. If you drew three circles after coming from the main menu, the TRY AGAIN will erase all three. When you have to draw a number of copies of the same shape, go back to the main menu after a few, so they will be saved in case the last one is bad.

CALL UP SAVED PICTURES

Now let's get down to a real drawing. Clear the screen, setting the foreground color to black and the background to white. Load in the starting space shuttle picture. Key DI to select DISK/SAVE/RESTORE. Select the DIRECTORY option (D). The list of all picture filenames on disk will show. Key the number corresponding to "P.START SHUTTLE". You will be returned to the disk option menu. Select the RESTORE option. The filename "P.START SHUTTLE" will appear. Since you want this, press <RETURN>. In about 30 seconds the picture will be loaded. (See it by pressing F7). Since we will want to add some other drawings to the shuttle picture, we must get them into the computer on the other screen. Do this by SWAP (key SW) (the new one should be blank with a green border). Now go to the DISK/SAVE/RESTORE function, read the DIRECTORY and RESTORE the picture called "P.TUTOR PARTS".

Use F7 to view the images from TUTOR PARTS a moon and star).

COPY IMAGES

Copy the moon as follows- Select the COPY function from the main menu and then the EXTR-BLK (Extract block) option. Use CTRL, the cursor keys and <RETURN> just as you did in the box. When the second corner is placed you are returned to the main menu. To try the copy back, select COPY and then COPY IN-BLK option. Select COMBINE and then IMAGE ONLY. Now the blue cursor is at the BOTTOM RIGHT corner of the image. Move the cursor around until its where you want (on a clear area of the TUTOR PARTS image). When <RETURN> is pressed, the moon image will be copied. Press CTRL and move the cursor to another area on the screen and press <RETURN> to write another copy. Press the F4 to erase these copies, and then press F1 to exit. Now SWAP and use the COPY IN-BLK to place the moon on the shuttle picture (upper left corner). SWAP to go back and extract the star and then put several stars on the shuttle picture.

OBJECTS

Now add an object:

The Object function is one of the most powerful in CADPAK. In addition to being somewhat like the COPY function where one copy can be copied into another area, it permits sizing and rotations and precise positioning. Each object must be defined as a 16 x 16 pixel image in the OBJECT EDITOR. For now, call up a set of objects from disk as follows. Select the OBJECTS/FONT MGR function. Then select DIRECTORY. Key in the number corresponding to "O.TUTOR OBJECTS" and press <RETURN>. The name selected will be shown for you to confirm by pressing <RETURN>. The set of objects will be read in. You will be returned to the main menu.

To use objects select the USE OBJECTS function. Select the NORM option.

The complete set will be shown. To put one on the screen, use the cursor keys to move the blue cursor over the one you want (the satellite in the upper left corner) and press and then press <RETURN>. The regular graphic screen will show. Press the CTRL key and move the cursor where you want the LOWER LEFT corner of the object to go. ACCUPOINT will position it precisely. Then press CTRL to position the upper right corner. As you move this corner, you are setting up the size of the copied object. The F4 key will correct a mistake and you can draw another copy of the object without going back to the main menu.

FILL

Complete the shuttle picture by using the FILL to fill the lower nose area, the wing, the engines with solid color. Fill the earth with another fill pattern and put a box around the title. You can fill the whole picture with the first fill pattern.

PRINT

Print the picture out by selecting the PRINT function. Then select either the small or large picture.

12.0 CADPAK TUTORIAL #2 (BOTH VERSIONS)

This tutorial will familiarize you with some the special font capabilities of CADPAK . If you do not have CADPAK loaded, do so. If you have been using the system, clear screen 1 and make sure you are on it (SCREEN 1 in the upper right corner of main menu).

1. Select the DISK/SAVE/RESTOR function.
2. Select the DIRECTORY option and look for file P.USA OUTLINE. Key that entry number (3).
3. Select RESTORE and then press <Return> to load it in. This is an outline of the USA and states which will find many uses.
4. Use the BOX function to put two legend boxes under the southern tip of TEXAS.
5. Select the FILL function and SOLID. Fill the one of the legend boxes and then the original 13 states: Vermont, New Hampshire, Connecticut, Rhode Island, New York, New Jersey, Pennsylvania, Delaware, Maryland, Virginia, North Carolina, South Carolina, Georgia. (you don't have to go back to the main menu, just set points at each state:
6. Return to the main menu and select FILL.
7. Select PATTERN.
8. Select USE then the diagonal bars. Use this to fill the other states admitted to the Union by 1850. Fill: the second legend box and Maine, Ohio, Indiana, Illinois, Michigan, Wisconsin, Iowa, Missouri, Arkansas, Louisiana, Texas, Mississippi, Alabama, Florida, Tennessee, Kentucky and California. Go back to the main menu.

-
9. Select the TEXT function. Select UP/LO and normal size. Place the cursor next to the solid filled legend and enter: "13 Original Colonies". Next to the pattern filled legend box enter "Admitted by 1850".
 10. Return to the main menu and select the OBJECT/FONT MGR function. Select the DIRECTORY option and find the 3-D FONT. Key the number (2) press <Return> and then Select READ and press <RETURN> to load it in.
 11. Select the TEXT function and select the SPECIAL FONT option. Set one point at the upper left corner, but leave some room above it for the letters. Then set another point above and to the right of it to select the minimum size special lettering. Then enter the text, something like "The United States by 1850". Note that in special font mode you can only delete one letter, so type slowly and carefully!

You can use this map for a state shape by using the point mode copy of a rectangle including the state. Then copy it into a blank screen setting the lower left in the lower left corner of the screen and then putting the upper right corner up and to the right enough to expand it. Then use RUBOUT and/or ZOOM to eliminate neighboring state lines.

13.0 CADPAK TUTORIAL #3 (BOTH VERSIONS)

This tutorial will acquaint you with some of the precision caling features of CADPAK-64.

Suppose you have your home on a lot, which is 150' wide by 100' deep. Your home is roughly in the center, and you want to see if you can fit a swimming pool onto your property (see illustration).

First, layout the lot. Clear the screen and select the Large size printout. A scale of 1"=20' will mean the drawing of the plot will be 7.5" (150'/20) x 5" (100'/20). This will fit into the large size paper (8.875 x 6.875 on the EPSON FX-80). Therefore select the default paper size and then make your external dimensions FEET and key 20 (feet) per inch on the paper.

Now to draw your plot, use a BOX. Set the first corner at coordinates 10,10 by pressing the Commodore key, pressing A (absolute coordinates) and then keying 10,10 and press <RETURN>. The cursor moves to 10,10 (feet) on your drawing.

Now press the Commodore key again and press R for relative distance input. Key the size of the plot (150,100) and press <RETURN>. The box is drawn. The lower left corner is 10,10 and the upper right is 160,110.

Go to the main menu text option and label the top as 150' and one side as 100'.

To draw the house, we need a rough outline (see below) which gives the outline in feet and we must know how far in it is from the lower left corner.

The easiest way to draw the house will be with the JOINTED lines option of the LINE command. We will use the Relative keyed input option so we can simply enter the distances in feet. The only trick is getting started. If we want to calculate the position of the lower left corner of the house, we could add the plot lower left corner (10,10) to the distance the house is from the corner (30,40) and start the house at 40,50.

Since that requires a calculator, lets try another way. The divide function lets you set one point relative to two others, at one or the other endpoints (0/1 or 1/1 fraction of the distance). For our house let' start this way:

Select the LINE function, SOLID lines and JOINTED lines options. Press the <- (left-arrow) key to start the divide function. Now key the first of the two points by pressing the Commodore key, then A then 10,10 and <RETURN>.

The border will turn purple again for the second point. Press the Commodore key, then R (relative) then key the relative distance 30,40 and press <RETURN>. Now you will see the divide screen showing both points and asking you for the fraction. Since we want to start at the second point, key 1,1 (meaning 1/1) of the distance. The cursor will move to the start point 40,50.

Now use the Commodore key and the R option for the following moves to outline the house:

R 0,30 up 30' for left side

R 60, 0 back wall

R 0,-40 down right side

R -20, 0 garage front

R 0,10 jog back to front wall

R -40,0 front wall


Return to main menu.

Use text to mark lengths on house (probably best to put these inside house).

Now you should add sidewalks, driveways, major trees, etc.

If you want to see if you can squeeze in a 20x40 pool, simply pick a starting point, with lightpen or drawing cursor, and use the Relative distance input of 20,30 to draw the box. If it looks bad, simply press F4 to erase it only and reposition the corner of the rectangle until it fits. You can then use the measure function to find out the distance from the house, etc.

Print this out and use a ruler to check the scaling (remember 1"=20'). If it doesn't check out, you may have selected the wrong size drawing (it should have been large) or you may have forgotten the sizing program or done it incorrectly. See "CADPAK SETUP".



14.0 TIPS ON USING CADPAK

14.1 DEFINING OBJECTS

It is very tempting to design four copies of an object, each in a different rotation (such as marker arrows for a drawing). The problem is that the only good reference point you have on any object when you are positioning it in a picture is the lower left corner. Therefore, if you design something such as a right pointing arrow and the positioning of the RIGHT END of the arrow is important, it will be almost impossible to do because the positioning of an object is based on the LOWER LEFT corner of the object. Instead, design it so that the arrow is pointing to the left and is as far down in the object as possible. Then when you go to use the object, choose either the reflection or rotation option and position the LOWER LEFT corner of the object (the point in this case) at the significant position on the diagram. Then move the light pen to the lower left of that point to set the sizing of the object and reflection or rotation, but this way the significant part of the object will be positioned properly. See the tutorial for an example of this.

Objects are not specifically dimensionable. An object is nothing more than a pixel pattern, and although it can be scaled up in multiples of its size, you can not make it a true exact sizing. Therefore if you wanted to have office furniture as a set of objects, you would have to accept the fact that these are only approximate sizes and not exact. Instead, you could use the 2nd screen to define specific sized shapes and then copy these onto your drawing and the size will be correct.

14.2 DESIGNING FONTS

When designing fonts, keep in mind that a special font is automatically proportionately spaced. CADPAK automatically senses the right most significant columns of each character and positions the next character against that row. (There is a minimum character size of 6 pixels) If you want the characters to flow together, such as in a script text, start each character against the left edge of the object block. If you do not want the characters to ever flow together, leave the left most column of pixels blank (such as on the OLD ENGLISH font included).

In designing fonts, remember that you will normally leave one or two blank rows under each character for descenders (such as under the g, y, q, etc.).

14.3 CURSORS

CADPAK was designed using sprites for the cursors used in drawing. This occasionally presents problems when you try to draw a very short line or very small box, etc. The cursors simply overlap and often cover up your reference point. The cursor priority adjustment was designed to get around this problem by moving all the cursors behind your screen reference point instead of in front of it. This can be done either with the F3 key or with the cursor priority adjustment on the utilities menu. Even with this, it is sometimes easier to go to the zoom function to draw very small things on the screen.

14.4 MAKING T-SHIRTS

You can use Cadpak-64 to make T-Shirts of various designs. The procedure is as follows:

Draw your design on screen 1.

Perform a COPY [AREA] function using POINT EXTRACT. Set both corners of the COPY OUT areas just inside the black border.

SWAP the screen.

Select MIRROR COPY IN-PT then perform COPY BACK function. Set first point in LOWER RIGHT corner of screen and second point in the UPPER LEFT corner of screen.

DUMP to printer using an image transferring type ribbon.



APPENDIX A - COLOR NUMBER TABLE

<u>COLOR NUMBER</u>	<u>COLOR</u>
1	BLACK
2	WHITE
3	RED
4	CYAN
5	PURPLE
6	GREEN
7	BLUE
8	YELLOW
9	ORANGE
10	BROWN
11	LIGHT RED
12	DARK GRAY
13	MEDIUM GRAY
14	LIGHT GREEN
15	LIGHT BLUE
16	LIGHT GRAY

APPENDIX B - PRINTERS / INTERFACES

BLACK & WHITE PRINTERS

Printer:	Commodore 1525 / 801 select <u>CBM 1525</u> printer
Interface:	none needed
Printer:	Commodore 1526 select <u>CBM 1526</u> printer
Interface:	none needed
Printer:	Okimate 10 Black & White select <u>Okimate 10 B&W</u> printer
Interface:	none needed
Printer:	Epson FX-80 Epson MX-80 Epson MX-100 Star Gemini 10 & 15 All work using <u>EPSON</u> printer
Printer:	Okidata Microline 92 select <u>OKIDATA</u> printer
Printer:	C Itoh 8510 Prowriter (Switch 1-7 open & 1-8 closed) select <u>PROWRITER</u> printer
Printer:	Siemens PT88 Inkjet select <u>SIEMENS PT/88</u> printer

INTERFACES:

Cardco '64 to Centronics model A

Secondary address 5

Printer Translate 0

ECX Inc C-6401

Switches- all 3 ON

Secondary address 0

Printer Translate 0

Microworld Electronics MW-302

Switches 3 & 4 ON

Secondary address 0

Printer Translate 1

Microworld Electronics MW-302

Switch 3 ON

Secondary address 0

Printer Translate 0

MSD Inc CPI

Switches 1,3,5 ON

Secondary address 0

Printer Translate 0

EPSON USER PORT INTERFACE

A special printer module is included which allows you to connect an EPSON printer (or lookalike) to the parallel user port on the '64. You will need only a parallel cable and appropriate connectors. The connections are:

'64 PIN	USE	CENTRONICS CONNECTOR PIN
A	GND	16
B	FLAG-BUSY	10
C-L	DATA	2-9
M	STROBE	1

COLOR PRINTERS

Printer: Okimate 10 Color
select Okimate 10 Color printer
Interface: none needed

Printer: C. Itoh Prowriter 8510SC
(SW 1-7 closed and 1-8 open)
select Prowriter color printer
Interface: same as Prowriter 8510 above.

Printer Installation Reference Guide

Our technical support staff finds that the most frequently-asked questions are those having to do with printer installation for the popular Abacus package CADPAK-64.

CADPAK-64 uses custom printer driver routines to achieve the highest quality output possible on a wide variety of printers. Your printer interface should be locked into *transparent* mode when running CADPAK-64. You can do this by using a specific secondary address or by sending a command in BASIC before starting CADPAK-64. Please refer to your printer interface manual for instructions to place the interface into *transparent* mode.

CADPAK-64 will work with a large number of printers not listed on the start-up screen. If your printer is not listed on the start-up screen, check your printer manual to see if it is EPSON graphics compatible or has a Commodore printer emulation mode. Many printers not listed will work correctly if they emulate an EPSON or Commodore printer.

The following information details the installation of most commonly-used printers/interfaces with CADPAK-64. If you have any other questions or suggestions, please contact our Technical Support department.

MPS801, 803, 1000 (Commodore inter-face only); Comrex CR-220; Epson Homewriter 10; Seikosha models ending with VC; any Star 10C or Star Gemini II	Load and run SIZE.PRG Select CBM 1525 Printer Printer Number=4 Secondary address=0 ASCII translate=0
MPS1000/non-Commodore interface	Select Epson Printer
MPS-802	Select CBM1526 Printer
Gemini 10x/Cardco G-Wiz	Select Epson Printer Printer - DIPs 1 & 2 on, 3 & 4 off Interface - all DIPs off

Panasonic KXP 1080/Cardco G+	Select Epson Printer Interface switch #7 off Secondary address=7 ASCII translate=0
Panasonic KXP 1080/Uprint	Enter OPEN 1,4,1 from BASIC (locks printer in transparent mode) Load SIZE.PRG Select Epson Printer Secondary address=1 ASCII translate=0
Star SG10/Tymac Connection	Lock interface into transparent mode Load SIZE.PRG Select Epson Printer
Star SG10/MW-350	Select 1525 Printer Set interface to emulate 1525 (switch #1 on) Secondary address=7
Star SG10/Xetec	Select Epson Printer Secondary address=5 ASCII translate=0 (or N)
Epson FX-85/Xetec	Lock interface into transparent mode Load and run SIZE.PRG Select Epson Printer Secondary address=5 ASCII translate=0 (or N)
Gemini 15X/Cardco G+	Select Epson Printer Secondary address=5

Okimate 192/Tymac Connection

Lock interface into
transparent mode
Load and run SIZE .PRG
Select Okidata
Secondary address=4
ASCII translate=1 (or Y)


SP1000A/Cardco G-Wiz

Select Epson Printer
Interface - DIPs 1 & 6 on,
the rest off


If you have found any difficulties or have found solutions for interfaces and printers not listed here, please contact Abacus' Technical Support Department.

Abacus Software
Technical Support
5370 52nd Street, SE
Grand Rapids, MI 49508


NOTE: Some printer configurations may still print circles as ovals (e.g., MPS801).



CADPAK-64 ABACUS Software / Adamsoft
45' 9.5"



CADPAK-64 for education




$\square = a^2$
 $\square = b^2$
 $\square = c^2$

Pythagoras says--
 $C^2 = A^2 + B^2$

GIVEN:
 $\angle C = 90^\circ$
 $\angle B = 90^\circ$

Abacus Software
 Adamsoft U.K.
 Tel: 0706-524304



CADPAK-64



Abacus Software
 Adamsoft U.K.

Telephone
 0706-524304

CADPAK-64 Abacus Software Page 1 of 1



APPENDIX C - 1351 MOUSE INSTRUCTIONS

CADPAK-64 now includes a version which works with the Commodore 1351 mouse.

Please note the following changes:

FOR ALL VERSIONS (Lightpen, Keyboard and Mouse):

The program SIZE.PRG for determining the dimensions for your printer is now on the "reverse" side of the diskette (the side WITHOUT the CADPAK-64 label).

To run it:

- insert the diskette into the disk drive with the label DOWN and close the drive door
- Type LOAD "SIZE.PRG", 8 <Return>
- Type Run <Return>

The program operates exactly as described in the manual (Section 5.1-Setting the dimensions for your printer) through step 11. In step 12 you will be asked to remove the diskette and TURN IT OVER (so the label is UP) before re-inserting it. The dimensioning information must be written on the "front" side of the diskette.

All of the other CADPAK-64 programs, fonts, objects, and pictures are on the labelled side of the diskette, so you will always have the diskette in the drive with the label UP.

There are no other changes to the lightpen or keyboard versions.

Commodore 1351 Mouse Version;

The mouse should be connected to joystick port 1 on the right side of the '64. Port 1 is the connector that is closest to the front of the computer.

Insert the diskette with the label up and type:

LOAD "MOUSECADPAK-64", 8 or simply

LOAD "M*", 8.

Follow the remaining steps 7-13 of section 6.0 LOADING CADPAK-64.

On the menu screen, the cursor appears as a small white arrow. You move the cursor by moving the mouse over your desktop. The cursors on the drawing screens operate with the mouse in the same way as with the keyboard version, except you move them by moving the mouse instead of the cursor keys.

You select a CADPAK function with the mouse by moving the arrow over the name of the function and then pressing the LEFT mouse button.

Setting a point with the mouse is similar. Move the mouse to position the cursor where you want it, then press the LEFT mouse button. This activates the ACCUPOINT mode. The border of the screen turns light blue to indicate ACCUPOINT mode. In ACCUPOINT, the mouse speed is reduced to make it easier to position the cursors accurately. When the point is where you want it, press the LEFT mouse button to set the point.

In the DRAW, POINT/SPRAY, and RUBOUT functions the cursor moves with the mouse. When you press the LEFT mouse button, writing (or erasing) begins and continues as you hold the button, and move the mouse.

The RIGHT mouse button is used to exit from a function. This is equivalent to pressing the F1 key in the keyboard version or pointing to the right screen border in the lightpen version.

On the main menu, pressing the RIGHT mouse button displays the current drawing screen as long as you hold the button.

On a secondary menu (such as the type of line), pressing the RIGHT mouse button returns you to the main menu.

In a drawing function (on the graphic screen) pressing the RIGHT mouse button ends the function and returns you to the main menu.

The only exception is in ACCUPOINT mode where the RIGHT mouse button displays the dimensions coordinates as you move the mouse, for cases when you need to set a point a certain distance from or at a specific point.

In addition to TRY AGAIN! on the main menu, you can press BOTH mouse buttons at the same time while in a drawing function to TRY AGAIN!

On the color selection screen, position the mouse pointer beneath the desired color and then press the LEFT mouse button to select the color.

In the ZOOM, OBJECT EDIT and PATTERN EDIT functions, the LEFT mouse button cause a point to be "flipped" as with the lightpen. If you press the C= key, at the same time as the LEFT mouse button, the point is FORCED ON. If you press the <- key at the same time as the LEFT mouse button, the point is FORCED OFF.


Note - Pressing and holding the LEFT mouse button during functions requiring text input (such as dimensions, filenames, and values) can insert spaces or other unwanted characters.

All other functions of CADPAK-64 work as described for the lightpen or keyboard versions.


The SOUND and sound commands have been disabled from the mouse version.



Top shelf books from Abacus



Detailed guide presents the 128's operating system, explains graphic chips, Memory Management Unit, 80 column graphics and commented ROM listings. 300pp \$19.95




Get all the inside information on BASIC 7.0. This exhaustive handbook is complete with commented BASIC 7.0 ROM listings. Coming Summer '86. 198pp \$19.95




Filled with info for everyone. Covers 80 column hi-res graphics, windowing, memory layout, Kernal routines, sprites, software protection, autostarting. 300pp \$19.95



Insider's guide for novice & advanced users. Covers sequential & relative files, & direct access commands. Describes DOS routines. Commented listings. \$19.95




Learn fundamentals of CAD while developing your own system. Design objects on your screen to dump to a printer. Includes listings for '84 with Simon's Basic. 300pp \$19.95



Introduction to programming, problem analysis, thorough description of all BASIC commands with hundreds of examples; monitor commands, utilities, much more. \$16.95



Presents dozens of programming quick-hitters. Easy and useful techniques on the operating system, stacks, zero-page, pointers, the BASIC interpreter and more. \$16.95



Essential guide for everyone interested in CP/M on the 128. Simple explanation of the operating system, memory usage, CP/M utility programs, submit files & more. \$19.95



ANATOMY OF C-64 Insider's guide to the '84 internals. Graphics, sound, I/O, kernal, memory maps, more. Complete commented ROM listings. 300pp \$19.95

ANATOMY OF 1541 DRIVE Best handbook on floppy drives. All. Many examples and diagrams. Commented 1541 ROM listings. 300pp \$19.95

MACHINE LANGUAGE C-64 Learn 6510 code write fast programs. Many samples and listings for complete assembler, monitor, & simulator. 200pp \$14.95

GRAPHICS BOOK C-64 - best reference covers basic and advanced graphics. Sprites, animation, hires, multicolor, lightpen, 3D-graphics, IRQ, CAD, projections, curves, more. 350pp \$19.95

TRICKS & TIPS FOR C-64 Collection of easy-to-use techniques: advanced graphics, enhanced data input, 275pp \$19.95

1541 REPAIR & MAINTENANCE Handbook describes the disk drive hardware. Includes schematics and techniques to keep 1541 running. 200pp \$19.95

ADVANCED MACHINE LANGUAGE Not covered elsewhere - video controller, interrupts, timers, clocks, I/O, real time, extended BASIC, more. 210pp \$14.95

PRINTER BOOK C-64/VIC-20 Understand Commodore, Epson-compatible printers and 1520 plotter. Packed: utilities, graphics dump; 3D-plot; commented MP\$801 ROM listings, more. 330pp \$19.95

SCIENCE/ENGINEERING ON C-64 In depth intro to computers in science. Topics: chemistry, physics, biology, astronomy, electronics, others. 350pp \$19.95

CASSETTE BOOK C-64/VIC-20 Comprehensive guide; many sample programs. High speed operating system fast file loading and saving. 225pp \$14.95

IDEAS FOR USE ON C-64 Themes: auto expenses, calculator, recipe file, stock lists, diet planner, window advertising, others. Includes listings. 200pp \$12.95

COMPILER BOOK C-64/C-128 All you need to know about compilers: how they work; designing and writing your own; generating machine code. With working example compiler. 300pp \$19.95

Adventure Gamewriter's Handbook Step-by-step guide to designing and writing your own adventure games. With automated adventure game generator. 200pp \$14.95

PEEKs & POKEs FOR THE C-64 Includes in-depth explanations of PEEK, POKE, USR, and other BASIC commands. Learn the "inside" tricks to get the most out of your '84. 200pp \$14.95

Optional Diskettes for books For your convenience, the programs contained in each of our books are available on diskette to save you time entering them from your keyboard. Specify name of book when ordering. \$14.95 each

C-128 and C-64 are trademarks of Commodore Business Machines Inc.

Abacus Software

5370 52nd Street SE Grand Rapids, MI 49508 Phone (616) 698-0330

Optional diskettes available for all book titles - \$14.95 each. Other books & software also available. Call for the name of your nearest dealer. Or order directly from ABACUS using your MC, Visa or Amex card. Add \$4.00 per order for shipping. Foreign orders add \$10.00 per book. Call now or write for your free catalog. Dealer inquiries welcome - over 1400 dealers nationwide.

Make Your Choice

C-64 or C-128

BASIC Compiler


Complete BASIC compiler and development package. Speed up your programs 5x to 35x. Compile to machine code, compact p-code or both. '128 version: 40 or 80 col, monitor output and FAST-mode operation. '128 version includes extensive 80-page programmer's guide. A great package that no software library should be without. C-64 \$39.95 C-128 \$59.95

BASIC Compiler

Speeds up your BASIC programs by 3 to 20 times. For C-64 and C-128

COBOL

Now you can learn COBOL, the most widely used commercial programming language, on your 128 or 64. COBOL Compiler package comes complete with syntax-checking editor, interpreter and symbolic debugging aids. New '128 version works with 40/80 column monitors and is quicker than the '64 version. C-64 \$39.95 C-128 \$59.95



Complete with Editor, Interpreter and Debugger

New C-128 Version!

Super Pascal Compiler

Complete system for developing applications in Pascal. Extensive editor. Standard J & W compiler. Graphics library. Added '128 features: RAM disk; 100K source/one drive or 250K/two; 80/40 column. If you want to learn Pascal or develop software using the best tool available, Super Pascal is your first choice. C-64 \$59.95 C-128 \$59.95

Super Pascal Language Compiler

Expand your programming horizons on your '64 and '128

Super C Compiler

For school or software development. Learn the C language on the '64 or '128. Compiles into fast machine code. Added '128 features: CP/M-like operating system; 60K RAM disk. Combine M/L & C using CALL; 51K available for object code; Fast loading; Two standard I/O libraries plus math & graphic libraries. C-64 \$59.95 C-128 \$59.95

Super C Language Compiler

Learn the the language of the 80's and beyond on your '64 and '128


New C-64 Version!

SpeedTerm

Let your 64 or 128 communicate with the outside world. Obtain information from various computer networks. Flexible, command driven terminal software package. Supports most modems. Xmodem and Punter transfer protocol. VT52 terminal emulation with cursor keys, large 45K capture buffer & user definable function keys.

New! C-64 \$39.95 C-128 \$39.95


Use your 64 or 128 to communicate with the outside world



SpeedTerm

CADpak


Easy-to-use interactive drawing package for accurate graphic designs. Dimensioning features to create exact scaled output to all major dot-matrix printers. Input via keyboard or lightpen. Two graphic screens for Copying from one to the other. DRAW, BOX, ARC, ELLIPSE, etc. available. Define your own library of symbols/objects—store up to 104 separate objects. C-64 \$39.95 C-128 \$59.95



CADPAK

Chartpak

Create professional quality charts fast—without programming. Enter, edit, save and recall data. Interactively build pie, bar, line or scatter graph. Set scaling, labeling and positioning. Draw charts 8 different formats. Statistical routines for average, standard deviation, least squares and forecasting. Use data from spreadsheets. Output to most printers. C-64 \$39.95 C-128 \$39.95



CHARTPAK

PPM

Comprehensive portfolio management system for the 64 and 128. Manage stocks, bonds, mutual funds, T-bills; record taxable or non-taxable dividends & interest income; reconcile each brokerage account cash balance with the YTD transaction file; on-line quotes through Dow Jones or Warner. Produces any type of report needed to analyze a portfolio or security. C-64 \$39.95 C-128 \$59.95

The Report									
Portfolio .ppm									
Date: 08/15/87 10:00 AM Grand Rapids, MI 49508									
\$11,128.88									
Symbol	Stock	Bond	CD	Rate	Yield	Cost	Market	Gain/Loss	
IBM	Stock			10.00%	10.00%	100.00	100.00	0.00	
MSFT	Stock			10.00%	10.00%	100.00	100.00	0.00	
GOOG	Stock			10.00%	10.00%	100.00	100.00	0.00	
DISC	Stock			10.00%	10.00%	100.00	100.00	0.00	
TELE	Stock			10.00%	10.00%	100.00	100.00	0.00	
WELLS	Stock			10.00%	10.00%	100.00	100.00	0.00	
AMER	Stock			10.00%	10.00%	100.00	100.00	0.00	
WELLS	Stock			10.00%	10.00%	100.00	100.00	0.00	
AMER	Stock			10.00%	10.00%	100.00	100.00	0.00	
WELLS	Stock			10.00%	10.00%	100.00	100.00	0.00	
AMER	Stock			10.00%	10.00%	100.00	100.00	0.00	
WELLS	Stock			10.00%	10.00%	100.00	100.00	0.00	
AMER	Stock			10.00%	10.00%	100.00	100.00	0.00	
WELLS	Stock			10.00%	10.00%	100.00	100.00	0.00	
AMER	Stock			10.00%	10.00%	100.00	100.00	0.00	
WELLS	Stock			10.00%	10.00%	100.00	100.00	0.00	
AMER	Stock			10.00%	10.00%	100.00	100.00	0.00	
WELLS	Stock			10.00%	10.00%	100.00	100.00	0.00	
AMER	Stock			10.00%	10.00%	100.00	100.00	0.00	
WELLS	Stock			10.00%	10.00%	100.00	100.00	0.00	
AMER	Stock			10.00%	10.00%	100.00	100.00	0.00	
WELLS	Stock			10.00%	10.00%	100.00	100.00	0.00	
AMER	Stock			10.00%	10.00%	100.00	100.00	0.00	
WELLS	Stock			10.00%	10.00%	100.00	100.00	0.00	
AMER	Stock			10.00%	10.00%	100.00	100.00	0.00	
WELLS	Stock			10.00%	10.00%	100.00	100.00	0.00	
AMER	Stock			10.00%	10.00%	100.00	100.00	0.00	
WELLS	Stock			10.00%	10.00%	100.00	100.00	0.00	
AMER	Stock			10.00%	10.00%	100.00	100.00	0.00	
WELLS	Stock			10.00%	10.00%	100.00	100.00	0.00	
AMER	Stock			10.00%	10.00%	100.00	100.00	0.00	
WELLS	Stock			10.00%	10.00%	100.00	100.00	0.00	
AMER	Stock			10.00%	10.00%	100.00	100.00	0.00	
WELLS	Stock			10.00%	10.00%	100.00	100.00	0.00	
AMER	Stock			10.00%	10.00%	100.00	100.00	0.00	
WELLS	Stock			10.00%	10.00%	100.00	100.00	0.00	
AMER	Stock			10.00%	10.00%	100.00	100.00	0.00	
WELLS	Stock			10.00%	10.00%	100.00	100.00	0.00	
AMER	Stock			10.00%	10.00%	100.00	100.00	0.00	
WELLS	Stock			10.00%	10.00%	100.00	100.00	0.00	
AMER	Stock			10.00%	10.00%	100.00	100.00	0.00	
WELLS	Stock			10.00%	10.00%	100.00	100.00	0.00	
AMER	Stock			10.00%	10.00%	100.00	100.00	0.00	
WELLS	Stock			10.00%	10.00%	100.00	100.00	0.00	
AMER	Stock			10.00%	10.00%	100.00	100.00	0.00	
WELLS	Stock			10.00%	10.00%	100.00	100.00	0.00	
AMER	Stock			10.00%	10.00%	100.00	100.00	0.00	
WELLS	Stock			10.00%	10.00%	100.00	100.00	0.00	
AMER	Stock			10.00%	10.00%	100.00	100.00	0.00	
WELLS	Stock			10.00%	10.00%	100.00	100.00	0.00	
AMER	Stock			10.00%	10.00%	100.00	100.00	0.00	
WELLS	Stock			10.00%	10.00%	100.00	100.00	0.00	
AMER	Stock			10.00%	10.00%	100.00	100.00	0.00	
WELLS	Stock			10.00%	10.00%	100.00	100.00	0.00	
AMER	Stock			10.00%	10.00%	100.00	100.00	0.00	
WELLS	Stock			10.00%	10.00%	100.00	100.00	0.00	
AMER	Stock			10.00%	10.00%	100.00	100.00	0.00	
WELLS	Stock			10.00%	10.00%	100.00	100.00	0.00	
AMER	Stock			10.00%	10.00%	100.00	100.00	0.00	
WELLS	Stock			10.00%	10.00%	100.00	100.00	0.00	
AMER	Stock			10.00%	10.00%	100.00	100.00	0.00	
WELLS	Stock			10.00%	10.00%	100.00	100.00	0.00	
AMER	Stock			10.00%	10.00%	100.00	100.00	0.00	
WELLS	Stock			10.00%	10.00%	100.00	100.00	0.00	
AMER	Stock			10.00%	10.00%	100.00	100.00	0.00	
WELLS	Stock			10.00%	10.00%	100.00	100.00	0.00	
AMER	Stock			10.00%	10.00%	100.00	100.00	0.00	
WELLS	Stock			10.00%	10.00%	100.00	100.00	0.00	
AMER	Stock			10.00%	10.00%	100.00	100.00	0.00	
WELLS	Stock			10.00%	10.00%	100.00	100.00	0.00	
AMER	Stock			10.00%	10.00%	100.00	100.00	0.00	
WELLS	Stock			10.00%	10.00%	100.00	100.00	0.00	
AMER	Stock			10.00%	10.00%	100.00	100.00	0.00	
WELLS	Stock			10.00%	10.00%	100.00	100.00	0.00	
AMER	Stock			10.00%	10.00%	100.00	100.00	0.00	
WELLS	Stock			10.00%	10.00%	100.00	100.00	0.00	
AMER	Stock			10.00%	10.00%	100.00	100.00	0.00	
WELLS	Stock			10.00%	10.00%	100.00	100.00	0.00	
AMER	Stock			10.00%	10.00%	100.00	100.00	0.00	
WELLS	Stock			10.00%	10.00%	100.00	100.00	0.00	
AMER	Stock			10.00%	10.00%	100.00	100.00	0.00	
WELLS	Stock			10.00%	10.00%	100.00	100.00	0.00	
AMER	Stock			10.00%	10.00%	100.00	100.00	0.00	
WELLS	Stock			10.00%	10.00%	100.00	100.00	0.00	
AMER	Stock			10.00%	10.00%	100.00	100.00	0.00	
WELLS	Stock			10.00%	10.00%	100.00	100.00	0.00	
AMER	Stock			10.00%	10.00%	100.00	100.00	0.00	
WELLS	Stock			10.00%	10.00%	100.00	100.00	0.00	
AMER	Stock			10.00%	10.00%	100.00	100.00	0.00	
WELLS	Stock			10.00%	10.00%	100.00	100.00	0.00	
AMER	Stock			10.00%	10.00%	100.00	100.00	0.00	
WELLS	Stock			10.00%	10.00%	100.00	100.00	0.00	
AMER	Stock			10.00%	10.00%	100.00	100.00	0.00	
WELLS	Stock			10.00%	10.00%	100.00	100.00	0.00	
AMER	Stock			10.00%	10.00%	100.00	100.00	0.00	
WELLS	Stock			10.00%	10.00%	100.00	100.00	0.00	
AMER	Stock			10.00%	10.00%	100.00	100.00	0.00	
WELLS	Stock			10.00%	10.00%	100.00	100.00	0.00	
AMER	Stock			10.00%	10.00%	100.00	100.00	0.00	
WELLS	Stock			10.00%	10.00%	100.00	100.00	0.00	
AMER	Stock			10.00%	10.00%	100.00	100.00	0.00	
WELLS	Stock			10.00%	10.00%	100.00	100.00	0.00	
AMER	Stock			10.00%	10.00%	100.00	100.00	0.00	
WELLS	Stock			10.00%	10.00%	100.00	100.00	0.00	
AMER	Stock			10.00%	10.00%	100.00	100.00	0.00	
WELLS	Stock			10.00%	10.00%	100.00	100.00	0.00	
AMER	Stock			10.00%	10.00%	100.00	100.00	0.00	
WELLS	Stock			10.00%	10.00%	100.00	100.00	0.00	
AMER	Stock			10.00%	10.00%	100.00	100.00	0.00	
WELLS	Stock			10.00%	10.00%	100.00	100.00	0.00	
AMER	Stock			10.00%	10.00%	100.00	100.00	0.00	
WELLS	Stock			10.00%	10.00%	100.00	100.00	0.00	
AMER	Stock			10.00%	10.00%	100.00	100.00	0.00	
WELLS	Stock			10.00%	10.00%	100.00	100.00	0.00	
AMER	Stock			10.00%	10.00%	100.00	100.00	0.00	
WELLS	Stock			10.00%	10.00%	100.00	100.00	0.00	
AMER	Stock			10.00%	10.00%	100.00	100.00	0.00	
WELLS	Stock			10.00%	10.00%	100.00	100.00	0.00	
AMER	Stock			10.00%	10.00%	100.00	100.00	0.00	
WELLS	Stock			10.00%	10.00%	100.00	100.00	0.00	
AMER	Stock			10.00%	10.00%	100.00	100.00	0.00	
WELLS	Stock			10.00%	10.00%	100.00	100.00	0.00	
AMER	Stock			10.00%	10.00%	100.00	100.00	0.00	
WELLS	Stock			10.00%	10.00%	100.00	100.00	0.00	
AMER	Stock			10.00%	10.00%	100.00	100.00	0.00	
WELLS	Stock			10.00%	10.00%	100.00	100.00	0.00	
AMER	Stock			10.00%	10.00%	100.00	100.00	0.00	
WELLS	Stock			10.00%	10.00%	100.00	100.00	0.00	
AMER	Stock			10.00%	10.00%	100.00	100.00	0.00	
WELLS	Stock			10.00%	10.00%	100.00	100.00	0.00	
AMER	Stock								

Selected Abacus Products for Commodore computers

Chartpak

Professional charting & graphing package for the C-64 or C-128

Charts and graphs are the most effective method of representing statistical data from business and science in a comprehensible, easy to digest format that quickly and accurately conveys numerical information.


Chartpak 64 or 128 makes it simpler than ever before for the professional who wants to easily create high-quality charts and graphs without any time-consuming programming. Chartpak's defaults let the user build professional quality charts or graphs right off the bat, or charts and graphs can be built to specification by selecting from Chartpak's easy-to-use menus. Every option is menu-driven—all the user has to do is enter the required data, choose the chart format and then watch the chart as it's drawn.

Chartpak quickly draws any one of 8 different formats of pie, bar, line and scatter graphs. Since Chartpak is an interactive software tool, changing a feature in the Chartpak graph is no problem. The user can immediately change the scaling, labels, axis, colors or bar-filling options at any time. Chartpak also has built-in features for statistical functions: least squares, regression, mean and exponential smoothing, and can be added to chart and graphs.

The 140-page manual contains several tutorials to walk the user through the easy process of building charts and graphs using extensive examples and sample charts. In addition, the screen menus are identified and cross-referenced to the user's guide for added convenience and ease of use.

When the user's created a chart or graph to satisfaction, they can get a hardcopy of it with most popular dot-matrix printers in either of two sizes. Many Chartpak users have reproduced these charts and graphs for reports and presentations.

The C-128 version that takes advantage of the added features and extra memory of the Commodore 128 computer. More data can be entered to build charts, and charts and graphs can contain more detail. In addition, Chartpak-128 gives 3 times the resolution of the 64 version. This permits an entire chart or graph to be previewed on the screen, or it can be scrolled to show the higher resolution detail.



Chartpak 64 and Chartpak 128 Features:

- Enter data manually, or use data straight from Basic 1, Multiplan and Calc Result
- Draws pie charts, vertical or horizontal line charts, vertical or horizontal grouped, mixed or stack bar charts, scatter diagrams
- Statistical routines include average, standard deviation, least squares, two-dimensional data, exponential smoothing
- Easy to use menu operations
- Handles up to four data sets totaling 200 points (more with C-128 version)
- Saves data and/or chart specifications separately
- Complete manual with Chartpak data reduction tutorials
- Printout in two different sizes
- Chartpak 128 has 3X the resolution of the '64 version

Hardware requirements:

Chartpak 64:

Commodore 64
1541 disk drive (or MSD disk drive).

Chartpak 128:

Commodore 128 with 40- or 80-column monitor
1571/1541 disk drive (or MSD disk drive)

Printers:

Commodore 1525 and 1526, MPS 801, Epson, Star Gemini, Okidata, Okimate, Siemens, others.

Suggested retail price:

C-64 version	\$39.95
C-128 version	\$39.95

Abacus Inc.
5370 52nd Street SE
Grand Rapids, MI 49508
Phone (616) 698-0330

Selected Abacus  Products for Commodore computers

PPM

Personal Portfolio Manager for the C-64 or C-128

"The program can be summed up in a few words: a customized database with advanced telecommunications features and a relatively sophisticated report generator. This combination is hard to beat on any micro-computer... don't pass this one by."

—Ted Salamone
Commodore Microcomputers

Personal Portfolio Manager is the most comprehensive portfolio management and analysis system available for the Commodore 64 and 128. It's for the investor who needs to manage his stock portfolio, obtain up-to-the-minute quotes and news, and perform selected analysis on securities. PPM is for the investor who needs to manage stocks, bonds, mutual funds, T-bills, record taxable or nontaxable dividends and interest income, obtain up-to-the-minute quotes and news, and perform selected analysis.

An account executive can keep a separate portfolio for each client and run a cross-reference report to find owners of selected securities. Portfolios can be kept for special interest (e.g. high tech, low risk income, junk bonds, etc.) and monitored by grouping. PPM's unique report generator lets the user produce any kind of report to analyze a portfolio or stock.


Additionally, the user can automatically update your portfolio using Warner Computer System. PPM logs on, updates the quotes, logs off and prints your reports using its *Autorun* feature. And PPM can handle large portfolios—the user can record up to 1000 open transactions on a single diskette.

Hardware requirements:

PPM-64
Commodore 64
1541 or 1571 disk drive

PPM-128
Commodore 128
1541 or 1571 disk drive

Modems (required for online data capture):
• Commodore Vicmodem, 1600, 1650, 1660
• Westridge
• Telelearning (and compatibles)



PPM Features:

- No copy protection on C-128 version, so your customers can make backups for their own use
- Manages stocks, options, bonds, mutual funds, T-bills or any other type of short or long-term investment
- **PPM-128** in 80-column runs up to twice the speed of the C-64 version
- New **TRANSFER** program transfers quotes to **PPM-128**
- New **CONVERT** program transfers PPM-64 data to PPM-128 data disk
- Records taxable or non-taxable dividends and interest income
- Reconciles each brokerage account cash balance with year-to-date transaction file
- Handles quotes entered manually or automatically through Warner Computer Services
- Retain up to 1000 open transactions on a single diskette (buys or short sells)
- Produces customized reports to suit your specific portfolio requirements
- *Autorun* feature sets time for PPM to long on, update quotes, log off and generate printer reports

Printers:

Commodore 1525 and 1526, MPS 801, Epson, Star Gemini, Okidata, Okimate, Siemens, others.

Suggested retail price:

C-64 version	\$39.95
C-128 version	\$59.95

Abacus Inc.
5370 52nd Street SE
Grand Rapids, MI 49508
Phone (616) 698-0330

SpeedTerm

Terminal Software
for both the C-128 and C-64

As a group, Commodore owners are one of the largest users of online communication services, such as CompuServ, The Source, Delphi and GENie. SpeedTerm was designed to handle the communication needs of this rapidly growing base of Commodore owners who access these services. Both programs are packaged together, so it's easy for you to order and stock SpeedTerm.

SpeedTerm sets a high standard in economical telecomputing software—this package offers more power per dollar than any other terminal program for the '64 and '128. SpeedTerm is a completely command-driven program that is easy to learn and use, yet provides great power and flexibility.

Even though SpeedTerm is simple in design, it packs numerous features that aren't found in others terminal packages. For instance, it supports both Xmodem and Punter file transfer protocols so that large files can be uploaded and downloaded without error. In addition to these popular file transfer protocols, SpeedTerm includes partial DEC VT52 terminal emulation. In addition to the standard options found in other terminal programs, manages a large 45K capture buffer and permits user defined function keys. SpeedTerm understands more than 30 powerful commands.


SpeedTerm is compatible with most of the inexpensive modems for the C-64 and C-128, and if properly interfaced, will function with all Hayes® compatible RS-232 modems. SpeedTerm's versatile capture buffer which can be used to both send and receive ASCII text files, or to record an online session.

The complete SpeedTerm package includes a 70 page manual with easy to understand tutorial.

Modems:

- Commodore 1600, 1650, 1660
- Hayes and Hayes-compatibles

Use your 64 or 128 to communicate with the outside world



SpeedTerm Features:

- Xmodem and Punter protocols for error-free filetransfer
- Supports partial VT52 terminal emulation
- Manages large capture buffer for recording long sessions (C-128 version has a 45K buffer, C-64 version has 24K)
- Use buffer to copy sequential files from disk to disk, and split files too large to fit into wordprocessors.
- Execute disk commands, e.g. scratching/rename files
- Lists sequential files on the screen or printer.
- Displays directory listings
- Send commands to the disk and read the error channel
- Has powerful command mode with over 30 commands
- Complete access to the DOS
- Permits flexible user-defined function keys
- Works with most popular modems
- Works with either 40 or 80 column monitors
- Includes 70-page manual with easy to understand tutorial

Hardware requirements:

SpeedTerm-64

- Commodore 64
- 1541/MSD or 1571 disk drive
- 40-column monitor

SpeedTerm-128

- Commodore 128
- 1541/MSD or 1571 disk drive
- 40- or 80-column monitor

Suggested retail price:

Program disk contains
both '64 and '128 versions

\$39.95

Abacus Inc.
5370 52nd Street SE
Grand Rapids, MI 49508
Phone (616) 698-0330

Selected Abacus Products for Commodore computers

TAS

Technical Analysis System for the C-64 or C-128

"TAS attempts to do a great deal... and delivers in a superb fashion. Furthermore, Abacus provides helpful user support. TAS is a great learning tool and a great value. A' for performance"

—Lyle M Johnson
Computerized Investment

Many sophisticated investors use technical indicators to determine when to buy and sell securities. Our popular, powerful Technical Analysis System package is a comprehensive charting and analysis package for these sophisticated stock market investors. TAS is for the serious stock market investor who requires the charting capabilities that only a computer can provide. TAS can analyze and chart these indicators to help him or her make investment decisions.


The Technical Analysis System package has features that were formally available only on much more expensive personal computers at a much higher cost. It allows the user to automatically update his/her portfolio through Dow Jones News/Retrieval Service or Warner Computer Service. Alternatively, the portfolio can be manually updated. TAS then draws a variety of charts and graphs that help the investor decide the "right" time to buy/sell stocks or bonds to realize the greatest profit.

The user can automatically download the indicators from Dow Jones/New Retrieval Service or Warner Computer Systems with TAS, or can manually enter, edit, review and recall this information. TAS can track high, low, close, volume, bid and ask by date, and can handle large data volumes, since the user can place 300 periods of information run up to 10 different stocks on one data diskette (even more with C-128/1571). If a user's portfolio is larger, he can use multiple data diskettes.

TAS-128 is based on our successful TAS-64, but has been very much enhanced by author Don Baulch at the request of users. This new '128 version includes macros, automatic unattended log-on, and quick-draw charts using from 1 to 4 windows.

Modems (required for online data capture):

- Commodore 1600, 1650, 1660
- Westridge
- Telelearning (and compatibles)



TAS Enhanced Versions

TAS Features:

- Extensive online data capture using Dow Jones/News Retrieval and Warner
- Plot 7 moving averages, 5 volume indicators, least squares, trading band, comparison and relative charts, and more
- Track 300 trading days for up to 10 stocks per disk—unlimited number of disks
- Autorun feature automatically plots charts for every stock on the data disk
- Vertical line plotting to identify monthly and yearly dates more precisely
- Pinpoint exact dates with accurate vertical line plotting—no more guessing
- Works with one or two disk drives

Hardware requirements:

TAS-64
Commodore 64
1541/MSD or 1571 disk drive

TAS-128
Commodore 128
1541/MSD or 1571 disk drive
80-column monitor

Printers:
Commodore 1525 and 1526, MPS 801, Epson, Star Gemini, Okidata, Okimate, Siemens, others.



Suggested retail price:

C-64 version **\$39.95**
C-128 version **\$59.95**

Abacus Inc.
5370 52nd Street SE
Grand Rapids, MI 49508
Phone (616) 698-0330

BeckerBASIC for GEOS

Now you can write BASIC applications to work with GEOS



Introducing **BeckerBASIC**. If you already know BASIC, you can now write your own GEOS applications in BASIC, easily.

BeckerBASIC gives you the power of over 270 new commands and functions.

Over 20 commands to make your programming easier. For example, TRACE, RENUMBER, DUMP, DIR, etc.

Packed with over 50 commands for easy disk access. Load and save blocks of memory or selected lines of your program. You can even PEEK and POKE into your disk drive's memory.

10 commands can be used for easier cursor control. Turn the cursor on and off. Set how quickly it flashes. Position it at any location on the screen.

20 commands are available for all your

hires programming needs. Create boxes, plot points, and draw lines.

18 additional commands are dedicated to creating sound. Set ring modulation, change the filter, alter the waveform and set the envelope.

Over 35 commands let you create and animate sprites directly. Alter their size, change their positions and check for collisions. Use the sprite editor to create sprites and icons.

Use the *Pulldown Menu Construction Set* and *Dialog Box Construction Set* to aid in the creation of your own applications

Royalty-free distribution of your **BeckerBASIC** applications.

Now anyone can create applications in BASIC to run with GEOS. Only \$49.95

For credit card orders call 1-616-698-0330

Call today or mail the coupon for your free catalog covering our complete line of software and books for the Commodore 64 and 128. Or ask for the location of the dealer nearest you. You can order direct by phone using your VISA, American Express or MasterCard or detach and mail your completed coupon. Dealer inquiries welcome—over 2400 nationwide.

Abacus

5370 52nd Street SE
Grand Rapids, MI 49508
Telex 709-101 • FAX 616/698-0325

GEOS is a trademark of Berkeley Software Corporation. Commodore is a trademark of Commodore Electronics Ltd.

If your Commodore dealer doesn't carry Abacus products, then have him order them for you. Or you can order direct using the following order blank or by calling—(616) 698-0330

Qty.	Product	Price	Total
1	BeckerBASIC for the Commodore 64	\$49.95	
In USA add \$4.00 for S & H per order. Foreign add \$12.00 per item.			
Michigan residents include 4% sales tax			
Total amount enclosed (US funds)			
Payment: ☐ MasterCard ☐ VISA ☐ American Express			
☐ Money Order ☐ Check			
Card No.		Exp.	
Name			
Address			
City		State	Zip
Phone No.			



